



FINAL REPORT

**FALL 2018  
SEMI-ANNUAL  
MONITORING REPORT**

**Waste Management of Canada  
Richmond Landfill  
Town of Greater Napanee, Ontario**

Submitted to:



**WASTE MANAGEMENT OF CANADA**

1271 Beechwood Road  
Napanee, ON K7R 3L1

Prepared by:

**BluMetric Environmental Inc.**

The Tower, The Woolen Mill  
4 Cataraqui Street  
Kingston, ON K7K 1Z7

Project Number: 180149-02

January 2019

## FALL 2018 SEMI-ANNUAL MONITORING REPORT

Waste Management of Canada  
Richmond Landfill  
Town of Greater Napanee, Ontario

Submitted to:



Waste Management of Canada  
1271 Beechwood Road  
Napanee, ON K7R 3L1

Prepared by:



BluMetric Environmental Inc.  
The Tower, The Woolen Mill  
4 Cataraqui Street  
Kingston, ON K7K 1Z7

Project Number: 180149-02

January 2019

## TABLE OF CONTENTS

<b>1.</b>	<b>INTRODUCTION.....</b>	<b>1</b>
<b>2.</b>	<b>METHODOLOGY .....</b>	<b>1</b>
2.1	PROGRAM SUMMARY.....	1
2.2	WATER SAMPLE COLLECTION AND LABORATORY ANALYSIS .....	2
2.3	GROUNDWATER ELEVATIONS.....	3
<b>3.</b>	<b>RESULTS AND DISCUSSION .....</b>	<b>3</b>
3.1	LIQUID LEVELS IN LEACHATE WELLS .....	5
3.2	GROUNDWATER RESULTS .....	5
3.2.1	Groundwater Elevations.....	5
3.2.2	Groundwater Analytical Results.....	6
3.2.3	Guideline B-7 Reasonable Use Limits (RULs) .....	8
3.2.4	Status of Monitoring Wells and Compliance with Ontario Regulation 903 .....	9
3.2.6	Groundwater Chemistry Quality Assurance / Quality Control (QA/QC) .....	9
3.3	SURFACE WATER RESULTS.....	10
3.3.1	Pond Elevations .....	10
3.3.2	Surface Water Monitoring Locations.....	10
3.3.3	Surface Water Flow .....	10
3.3.4	Surface Water Analytical Results .....	11
3.3.5	Surface Water Quality Assurance / Quality Control (QA/QC) .....	11
3.4	SUBSURFACE GAS SAMPLING.....	12
3.5	ANNUAL SUMMARY .....	12
3.6	ADDITIONAL INVESTIGATIONS .....	13
<b>4.</b>	<b>SUMMARY, CONCLUSIONS AND RECOMMENDATIONS .....</b>	<b>14</b>
4.1	GROUNDWATER.....	15
4.2	SURFACE WATER .....	16
4.3	SUBSURFACE GAS.....	16
4.4	LEACHATE GENERATION.....	16
<b>5.</b>	<b>LIMITING CONDITIONS.....</b>	<b>16</b>



## LIST OF TABLES

Table 1:	Summary of Environmental Monitoring Program
Table 2:	Analytical Parameters for Water and Leachate Samples
Table 3:	Groundwater Elevation Monitoring Locations
Table 4a:	Groundwater Elevations – September 13, 2018
Table 4b:	Groundwater Elevations – October 12, 2018
Table 5a:	Groundwater Quality Results – October 15-18, 2018
Table 5b:	Groundwater Quality Results and Reasonable Use Limits – October 15-18, 2018
Table 6a:	Surface Water Characteristics – August 9, 2018
Table 6b:	Surface Water Characteristics – October 16, 2018
Table 7a:	Surface Water Quality Results – August 9, 2018
Table 7b:	Surface Water Quality Results – October 16, 2018
Table 8:	Subsurface Gas Monitoring Results – October 17, 2018
Table 9:	Additional Investigations

## LIST OF FIGURES

Figure 1:	Site Plan and Monitoring Locations
Figure 2a:	Shallow Groundwater Flow Zone Potentiometric Surface – September 13, 2018
Figure 2b:	Shallow Groundwater Flow Zone Potentiometric Surface – October 12, 2018
Figure 3a:	Intermediate Bedrock Groundwater Flow Zone Potentiometric Surface – September 13, 2018
Figure 3b:	Intermediate Bedrock Groundwater Flow Zone Potentiometric Surface – October 12, 2018
Figure 4:	Shallow Flow Zone Concentrations
Figure 5:	Intermediate Bedrock Flow Zone Concentrations

## LIST OF APPENDICES

Appendix A:	Monitoring Well Inventory
Appendix B:	Results from Analytical Quality Assurance / Quality Control (QA/QC) Program
Appendix C:	Time-Concentration Plots from Groundwater Trigger Wells



## 1. INTRODUCTION

The purpose of this report is to present results and to provide an interpretation of the data that were collected during the summer and fall 2018 monitoring events at the Waste Management of Canada Corporation (WM) Richmond Landfill.

The WM Richmond Landfill is approved as a 16.2 hectare waste disposal (landfilling) facility within a total site area of 138 hectares, located on parts of Lots 1, 2 and 3, Concession IV of the former Township of Richmond, now in the Town of Greater Napanee, Ontario.

## 2. METHODOLOGY

### 2.1 PROGRAM SUMMARY

The summer and fall 2018 monitoring events were conducted in accordance with the requirements outlined in the revised interim Environmental Monitoring Plan (EMP; Revision No. 05) dated April 15, 2016, as specified in the Environmental Compliance Approval (ECA) number A371203, issued by MOE January 9, 2012 and amended by Notice No. 1 dated May 3, 2013 and Environmental Review Tribunal (ERT) Order dated December 24, 2015.

The site layout and monitoring locations are shown on Figure 1. The monitoring programs for groundwater, surface water, leachate and landfill gas are summarized in Table 1.

The summer monitoring event was conducted between August 9 and September 13, 2018. The activities completed include the following:

- Surface water sampling was conducted on August 9, 2018 from locations S2, S3, S18, S19 and S20. No samples were collected from locations S4R, S5, S6, S7 or S8R because they were dry. Surface water samples were analyzed for surface water inorganic and general parameters and for 1,4-dioxane, as listed in Table 2. One field duplicate was collected during the summer surface water sampling event.
- Groundwater monitoring wells installed in the shallow and intermediate bedrock flow zones (see Table 3) were monitored for water levels on September 13, 2018. No water level was measured at groundwater monitors M15, M18, M23, M53-4, M58-4, M68-4 and M70-3 because they were dry, or from M19 because it is damaged;
- Water levels were recorded at the staff gauges installed at the three ponds located on site between the landfill and Beechwood Road; and,
- Liquid levels were measured in landfill leachate wells on September 13, 2018.



The fall monitoring event was conducted between October 12 and 18, 2018. The activities completed include the following:

- Groundwater monitoring wells installed in the shallow and intermediate bedrock flow zones (see Table 3) were monitored for water levels on October 12, 2018. No water levels were measured at groundwater monitors M18 and M23 because they were dry nor M19 because it is damaged;
- Water levels were recorded at the staff gauges installed at the three ponds located on site between the landfill and Beechwood Road on October 12, 2018;
- Liquid levels were measured in landfill leachate wells on October 12, 2018;
- Groundwater monitoring wells were sampled between October 15 and 18, 2018. No samples were collected from monitoring wells M58-4 because it was damaged and M85 because it was dry. Samples were analyzed for the suite of groundwater inorganic and general parameters and Volatile Organic Compounds (VOCs) listed in Table 2;
- Surface water sampling was conducted on October 16, 2018 from locations S2, S3, S18, S19 and S20. No samples were collected from locations S4R, S5, S6, S7 and S8R because they were dry. Surface water samples were analyzed for surface water inorganic and general parameters and for 1,4-dioxane, as listed in Table 2;
- Landfill gas monitoring was conducted on October 17, 2018. Field measurements were made with a RKI Eagle probe calibrated to methane gas response at six gas monitors (GM1, GM3, GM4-1, GM4-2, GM5 and GM6); and,
- A total of six Quality Assurance/Quality Control (QA/QC) samples were collected during the fall sampling event, including three field duplicate samples, two trip blanks and one field blank. De-ionised water for analysis of blank samples was supplied by the laboratory.

## 2.2 WATER SAMPLE COLLECTION AND LABORATORY ANALYSIS

Groundwater and surface water samples were collected in accordance with accepted industry protocols. Groundwater samples were collected using dedicated Waterra inertial lift pumps connected to dedicated polyethylene tubing. Three casing volumes of water were purged from each monitoring well prior to the collection of groundwater samples. During purging, readings for pH, temperature, conductivity and oxidation-reduction potential were recorded on a regular basis. The stabilization of the parameters was used to assess when well purging was complete. Low producing wells were purged dry and allowed to recover prior to sampling. If the monitoring well had not recovered sufficiently for sampling within 24 hours, the monitor was considered dry and a sample was not collected.



Surface water samples were collected using a clean bottle where water depth was sufficient; at sampling locations where water depth was an issue, a 50 cc syringe was used to carefully collect the surface water as not to disturb the bottom sediments. Surface water sampling locations were sampled from downstream to upstream to prevent any re-suspension of sediment impacting the downstream sampling locations. The pH, temperature, conductivity, dissolved oxygen and oxidation-reduction potential of the surface water were obtained in the field at all surface water sampling points while minimizing disturbance of the bottom sediment.

All water samples were placed in bottles supplied and prepared by the laboratory. The samples were packed in coolers with ice and shipped by courier to the laboratory. All samples were analysed by Maxxam Analytics Inc. of Mississauga, ON, which is accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA). Table 2 presents a summary of groundwater and surface water analytical parameters.

### 2.3 GROUNDWATER ELEVATIONS

Water levels were recorded to the nearest 0.005 m using an electronic water level meter for the groundwater monitoring wells listed in Table 3, grouped in relation to their location relative to the landfill footprint and groundwater flow zone monitored.

## 3. RESULTS AND DISCUSSION

Background information concerning the site geology and hydrogeology was described in detail in the Site Conceptual Model (SCM) report<sup>(1)</sup> and updated based on results from subsequent hydrogeological investigations<sup>(2,3,4,5,6)</sup>, and is summarized here. The SCM report describes the groundwater flow conditions at the Richmond Landfill.

---

<sup>1</sup> *Site Conceptual Model Report, WM Richmond Landfill*, prepared by Dr. B.H. Kueper and WESA Inc., October 2009

<sup>2</sup> *Supporting Document, Application to Amend Environmental Compliance Approval No. A371203, Waste Management Richmond Landfill Site*, prepared by BluMetric Environmental Inc., March 2015

<sup>3</sup> *Site Conceptual Model Update and Contaminant Attenuation Zone Delineation, Waste Management Richmond Landfill Site*, prepared by BluMetric Environmental Inc., January 2016

<sup>4</sup> *Addendum to Site Conceptual Model Update and Contaminant Attenuation Zone Delineation, Waste Management Richmond Landfill Site*, prepared by BluMetric Environmental Inc., April 2016

<sup>5</sup> *Site Conceptual Model Update and Contaminant Attenuation Zone Delineation, Waste Management Richmond Landfill Site*, prepared by BluMetric Environmental Inc., July 2017

<sup>6</sup> *Site Conceptual Model Update and Contaminant Attenuation Zone Delineation, Waste Management Richmond Landfill Site*, prepared by BluMetric Environmental Inc., October 2018



Based on the results from extensive studies conducted previously at the site, the basic hydrogeological framework for the facility has been defined as follows:

- the active groundwater flow zone at the site extends to a depth of approximately 30 m below the top of bedrock;
- the shallow groundwater flow zone is conceptualized as the overburden, the overburden-bedrock contact and the upper one to two metres of bedrock;
- the direction of groundwater flow in the shallow flow zone is strongly influenced by topography;
- the intermediate bedrock flow zone extends from one to two m below top of bedrock to a depth of approximately 30 m below top of bedrock;
- groundwater flows through a network of fractures in the upper 30 m of bedrock;
- the dominant fracture orientation is horizontal to sub-horizontal; however, vertical to sub-vertical fractures are present providing hydraulic connection between horizontal fractures;
- hydraulic connections of fractures exist in the intermediate bedrock flow zone to the west, south and east of the site (horizontal and vertical connections);
- intermediate bedrock flownets show that groundwater flow directions are variable with season and generally flows to the west from the western edge of the landfill, to the southeast from the southern edge of the landfill, to the south along the eastern edge of the landfill, and north to northwest from the northern limit of the landfill;
- the hydraulic conductivity of the intermediate bedrock is lower to the north and east of the landfill compared to other areas of the site, implying that the rate of groundwater flow is lower than in areas immediately south, southeast and west of the landfill;
- south of the landfill, the intermediate bedrock flow zone has distinct areas of interacting hydrogeological zones which are not isolated from one another, but are distinct based on hydraulic conductivity, water level variations and the rate of response to recharge events; and,
- groundwater monitoring wells in the southern portion of the proposed CAZ have static groundwater elevations that are much deeper than wells further north in the CAZ; these deep groundwater elevations appear to be controlled by karst systems confirmed to exist in the southern portion of the proposed CAZ, as discussed in the latest update to the SCM<sup>(6)</sup>.





### 3.1 LIQUID LEVELS IN LEACHATE WELLS

Liquid levels were measured in the two landfill leachate wells on September 13 and October 12, 2018:

- The liquid level at LW-P1 was 147.31 and 146.98 meters above sea level (masl), respectively; and,
- The liquid level at LW-P2 was 149.60 and 149.81 masl, respectively.

### 3.2 GROUNDWATER RESULTS

#### 3.2.1 Groundwater Elevations

Groundwater elevations were measured on September 13 and October 12, 2018 from monitoring wells listed in Table 3, and are presented in Tables 4a and 4b, respectively. An inventory of all monitoring well locations is provided in Appendix A. Groundwater elevation contours within the shallow groundwater flow zone are shown on Figure 2a (summer) and Figure 2b (fall), while Figure 3a (summer) and Figure 3b (fall) show groundwater elevation contours for the intermediate bedrock flow zone. Groundwater flow directions were inferred by interpolating the water elevations from wells screened within the corresponding groundwater flow zone, and are consistent with historical results.

The summer and fall 2018 shallow groundwater contours (Figures 2a and 2b, respectively) show that the Empey Hill drumlin southwest from the landfill creates a flow divide, with shallow groundwater being directed both to the north and the south towards areas of lower hydraulic heads. The water level from shallow bedrock monitor M19 (damaged) was not used to prepare the summer or fall 2018 groundwater contours. Additionally, monitors M15, M18, M23, M53-4, M58-4, M68-4 and M70-3 were dry during the summer 2018 monitoring event, and the water level at M174 could not be measured as it was greater than 30 meters below the top of casing (beyond the length of the water level tape). Monitors M178R-2 and M178R-3 were flowing artesian during the summer sampling event; however, the pressure gauge did not register. A pressure of 1 psi was used to estimate water levels at these locations. Monitors M18 and M23 were dry during the fall 2018 monitoring event.

North of the landfill, shallow groundwater converges towards Marysville Creek in the area immediately east of County Road 10 (Deseronto Road), while shallow groundwater flow in the southern portion of the site converges on Beechwood Ditch and the southern pond system.



Shallow groundwater east of the landfill is influenced by a local zone of higher water levels in the vicinity of monitoring well M96; shallow groundwater north of M96 flows to the north-northwest and ultimately Marysville Creek, while groundwater south of M96 flows to the south-southwest, towards Beechwood Ditch and the ponds.

The summer and fall 2018 intermediate bedrock zone contours are presented on Figures 3a and 3b, respectively. On the landfill property, groundwater in this hydrostratigraphic unit generally flows to the north, west, and south-southeast relative to the landfill.

Groundwater flow for the intermediate bedrock in the area of well-connected fractures south of the landfill and east of the landfill access road can be distinguished by periods of higher groundwater levels and periods of lower groundwater levels. During periods of high groundwater levels, the groundwater generally flows south-southeast. During periods of lower water levels, as observed during the summer 2018 monitoring event, groundwater flow is oriented toward the central portion of the well-connected area immediately south of the landfill, and continues toward the east-southeast as it moves further south of the landfill. Water levels from intermediate bedrock monitors M71 (damaged) and M191 (low permeability wells with water level interpreted as not being representative of static groundwater conditions) were not used to prepare the summer or fall 2018 groundwater contours. Additionally, intermediate bedrock zone monitoring wells located farther to the south (e.g., M173, M174, M181-1, M181-2, M182, M185-1, M187 and M189) were not considered in the groundwater contour interpolation because they exhibit much lower hydraulic heads, and appear to be part of a separate group of hydraulically responsive wells within the intermediate bedrock flow zone. This subset of wells appears to be influenced by karst systems that were identified in the southern part of the proposed CAZ. Additional details from the karst assessment in the area south and southeast of the Site have been provided under separate cover<sup>(5)</sup>.

### 3.2.2 Groundwater Analytical Results

Groundwater monitoring results from the wells sampled in fall 2018 as part of the EMP, as well as those from the additional sampling conducted in accordance with ECA Condition 8.5(c)iv, are presented in Table 5a. Groundwater quality data for the fall 2018 monitoring event are consistent with historical results.

Alkalinity, ammonia and 1,4-dioxane results are shown for the Shallow and Intermediate Bedrock Flow Zones on Figures 4 and 5, respectively.



### 3.2.2.1 Shallow Groundwater Flow Zone

As shown in Table 5a, slightly elevated concentrations of a number of water quality parameters (e.g., alkalinity, boron, chloride, conductivity, DOC, sodium and/or TDS) were observed in some shallow groundwater zone monitoring wells located in close proximity to the landfill footprint, north and northwest from the unlined portion of the landfill (e.g., M66-2, M86, M101, M103 and M104). 1,4-dioxane was detected at monitoring wells M101, M103 and M104, and 1,1-dichloroethane was detected at monitoring well M101. The approximate extents of leachate impacted shallow groundwater, consistent with those delineated from recent hydrogeological investigations<sup>(6)</sup>, are shown on Figure 4.

Monitor M54-4, located approximately 200 m south of the landfill footprint, also exhibited slightly elevated alkalinity, conductivity and TDS, as well as low but detectable concentrations of chlorinated VOCs (e.g., 1,1,1-trichloroethane, 1,1-dichloroethane, cis-1,2-dichloroethylene, tetrachloroethylene, trichloroethylene and vinyl chloride). An assessment of the impacts at shallow monitoring well M54-4, attributed to surface contamination from historical local sources rather than from landfill leachate, was submitted recently under separate cover<sup>(7)</sup>.

In other areas of the Site, there is no evidence of groundwater impacts away from the landfill footprint in the shallow groundwater flow zone. Isolated occurrences of elevated concentrations of water quality parameters (i.e., one or two parameters per sample) are seen elsewhere on the Site.

### 3.2.2.2 Intermediate Groundwater Flow Zone

Analytical results from intermediate bedrock groundwater monitors sampled in fall 2018 were generally consistent with historical results. North of the landfill, elevated concentrations of water quality parameters and detectable 1,4-dioxane concentrations were observed at monitors M6-3 and OW4, which are located in close proximity to the landfill footprint. These results indicate the presence of leachate impacts at these locations. However, despite moderate concentrations of some parameters (e.g., alkalinity at OW1, M5-3 and M75), no impacts from the landfill are apparent further north from the landfill footprint and near Marysville Creek (e.g., at OW1, M5-3, M75, M82-1 and M82-2).

---

<sup>7</sup> *Assessment of Chlorinated VOC Impacts at Shallow Groundwater Monitoring Well M54-4, Waste Management Richmond Landfill, Town of Greater Napanee*, BluMetric Environmental Inc., July 2017



South and southeast of the landfill, the presence of 1,4-dioxane and elevated concentrations of alkalinity (typically greater than 400 mg/L where 1,4-dioxane is present), DOC, chloride and TDS indicate groundwater impacts from the landfill at several monitoring well locations (e.g., M9-2, M9-3, M64-2, M108, M109-1, M110-1, M114-1, M121, M123, M167, M168, M170, M172, M178R-2, M178R-3, M178R-4 and M192). Several monitoring wells downgradient of these impacted wells (e.g. M177, M179, M185-1, M185-2, M186, M187, M188-1 and M190) do not show impacts associated with landfill leachate (i.e. no 1,4-dioxane detected and alkalinity concentrations of 360 mg/L or lower) thus defining the limit of the groundwater plume. The approximate extents of leachate impacted groundwater in the intermediate bedrock flow zone, consistent with those delineated from recent hydrogeological investigations<sup>(6)</sup>, are shown on Figure 5. Other locations south and southeast of the landfill with elevated concentrations of chloride, sodium, TDS, and/or BTEX compounds (e.g., M106, M185-1, M186, M70-2), are indicative of naturally poor quality connate (and often saline) groundwater. These pockets of naturally poor quality groundwater are isolated and do not reflect any widespread or significant upwelling of saline groundwater. Wells sampled in the western part of the landfill site (e.g., M72, M74 and M82-1) exhibit concentrations of water quality parameters that are relatively low and continue to reflect background conditions.

### 3.2.3 Guideline B-7 Reasonable Use Limits (RULs)

Constituent concentrations from selected monitoring wells located within the low-head areas of the WM Richmond Landfill in both the Shallow and Intermediate Bedrock Groundwater Flow Zones are compared to the RULs derived from laboratory analytical results (Table 5b). The RULs reported in Table 5b for leachate indicator parameters and trigger wells were presented in the interim EMP (Revision No. 05) dated April 2016, including 1,4-dioxane for which the site-specific RUL of 0.001 mg/L was set as required by the ERT Order dated December 24, 2015.

All results for 1,4-dioxane at trigger wells in the shallow and intermediate bedrock flow zones were below the RUL of 0.001 mg/L, with the exception of M178R-2, M178R-3 and M178R-4 with detectable concentrations that are consistent with historical data.

In the shallow groundwater zone, slightly elevated concentrations of a number of inorganic or general water quality parameters above their respective RUL (e.g., alkalinity, DOC, iron, manganese, sodium, and/or TDS) were observed in monitoring wells M54-4, M66-2, M67-2, M80-2 and OW37-s.



Slightly elevated concentrations of a number of water quality parameters above their respective RUL (e.g., alkalinity, chloride, DOC, iron, manganese, sodium, and/or TDS) were also observed in some intermediate groundwater flow zone monitoring wells (e.g., M82-1, M82-2, M106, M178R-2, M178R-3, M178R-4 M179, M185-1, M186 and M190).

### **3.2.4 Status of Monitoring Wells and Compliance with Ontario Regulation 903**

During the fall 2018 monitoring event, the condition of groundwater monitoring wells included in the EMP was inspected. Any repairs, such as new locks, labels or well caps, were made as necessary. Watertight casings and seals remain in place at all monitors to ensure that surface water or foreign materials cannot enter groundwater monitoring wells. All groundwater monitoring wells are fitted with a vermin proof cap to meet the requirements of Ontario Regulation 903 and are locked to provide protection against vandalism as per Waste Management standard operating procedure and in line with industry best practices.

Shallow groundwater monitoring wells M19, M58-4 and M68-4 are damaged and it is recommended that they be decommissioned when a revised EMP is approved as they cannot be repaired. These wells are considered unnecessary because flow in the shallow groundwater flow zone can be adequately assessed across the site without them.

### **3.2.6 Groundwater Chemistry Quality Assurance / Quality Control (QA/QC)**

An evaluation of QA/QC data (from duplicate and blank samples) is included in Appendix B. A standard margin of error of 20% relative percent difference (RPD) between regular and duplicate samples was deemed acceptable for field duplicates. In general, the comparison between samples and duplicates shows very good correlation for the majority of analyzed constituents.

All parameters for groundwater duplicate QA/QC sampling were within the 20% margin of error, with the exception of manganese (detected in the regular and duplicate samples at and slightly above the laboratory's reportable detection limit (RDL) of 0.002 mg/L, and therefore within the acceptable error margin established at 5 times the RDL). All parameters were near or below the RDL in the field blanks.



### **3.3 SURFACE WATER RESULTS**

#### **3.3.1 Pond Elevations**

Staff gauges are installed in the three ponds on the south side of the landfill labeled SG1, SG2 and SG3 (Figure 1). Staff gauge locations and pond elevations measured on September 13 and October 12, 2018 are shown on Figures 2a and 2b.

#### **3.3.2 Surface Water Monitoring Locations**

The two water courses that may receive surface water/storm water runoff from the Richmond Landfill site are Marysville Creek to the north of the waste mound and Beechwood Ditch to the south (Figure 1). Beechwood Ditch is a man-made surface water course that flows from the east onto WM property. It then flows west across a portion of the site before again crossing Beechwood Road and travelling southwest to cross County Road 10, and joins Marysville Creek east of Highway 49 and north of Highway 401. Both Beechwood Ditch and Marysville Creek flow intermittently in the vicinity of the landfill. Marysville Creek has some base flow locally, and flows on a continuous basis west of County Road 10 (Deseronto Road). Marysville Creek eventually discharges into the Bay of Quinte at Hungry Bay.

An ephemeral unnamed local surface water course is present in the central portion of the proposed CAZ boundary, originating from a small man made pond located directly east of Quarry Road (see Figure 1). Surface water flows west from this pond over a distance of approximately 600 m along a topographically low area, to a second pond located near monitoring well M187 and finally to a local topographic depression located approximately 75 m farther west, where water, when flowing, enters into the ground into a near-surface karst feature.

Surface water monitoring locations are shown on Figure 1. No samples were collected from sampling locations S4R, S5, S6, S7 and S8R in August or October 2018 because they were dry.

#### **3.3.3 Surface Water Flow**

Visual observations of surface water flow and general water characteristics for the summer and fall sampling programs are summarized in Tables 6a and 6b, respectively. Surface water flow velocities were not measured at any location because of insufficient flow conditions.



### 3.3.4 Surface Water Analytical Results

The analytical results from surface water locations sampled during the summer and fall 2018 sampling events are presented in Tables 7a and 7b, respectively.

Surface water quality results were compared to Provincial Water Quality Objectives (PWQO). Background surface water quality was monitored on site at upstream station S2 for Marysville Creek. Background surface water quality was monitored at upstream station S18 for the unnamed local water course located in the central portion of the CAZ. Storm water runoff from the existing landfill area flows to one of three storm water sedimentation retention ponds, located to the northeast, northwest and south of the landfill footprint. Sampling location S3 is located near the downstream property boundary along Marysville Creek.

Constituents analysed in surface water samples collected during the summer 2018 sampling event were below their respective PWQO, with the exception of total phosphorous at all locations, copper at location S2, and iron at locations S3, S18 and S20. Parameters analysed in surface water samples collected during the fall 2018 sampling event were all below PWQO, with the exception of total phosphorous at upstream locations S2 and S18, cobalt at location S2 and iron at locations S2 and S3.

Results from summer and fall 2018 are consistent with historical results and indicate that the landfill is not causing adverse impacts to surface water quality.

### 3.3.5 Surface Water Quality Assurance / Quality Control (QA/QC)

An evaluation of QA/QC data (from duplicate and blank samples) is included in Appendix B. A standard margin of error of 20% was deemed acceptable for field duplicates. In general, the comparison between regular samples and duplicates shows very good correlation for the majority of analyzed constituents.

All parameters for the summer sampling round surface water field duplicate sample (location S20) were within the 20% margin of error, with the exception of cobalt, iron, phosphorous and total suspended solids (TSS). Cobalt and TSS were within the acceptable error margin established at 5 times the laboratory's reportable detection limit (RDL). All parameters for the fall sampling round surface water field duplicate sample (location S2) were within the 20% margin of error, with the exception of TSS.



### 3.4 SUBSURFACE GAS SAMPLING

On October 17, 2018, BluMetric inspected the subsurface gas monitoring probes and measured methane concentrations at all locations. The locations of the gas monitors are shown on Figure 1 and results are provided in Table 8. Measurements of gas wells were between 0 and 20 ppm, well below the LEL for methane of 5% by volume in air (or 50,000 ppm).

### 3.5 ANNUAL SUMMARY

A comparative review of groundwater quality results between this and previous sampling events indicates that constituent concentrations vary over time but for the most part have remained relatively consistent over the current calendar year and over the past five years or more. Depending on which monitoring point and more importantly the time scale considered, conflicting trends in concentrations can occur sporadically. However since implementing the revised EMP dated June 29, 2010, the majority of the patterns have been observed to be seasonally variable but relatively similar.

Where sufficient historical data are available, alkalinity, chloride, dissolved organic carbon (DOC), iron, manganese, sodium and total dissolved solids (TDS) concentration data were reviewed for all groundwater trigger wells listed in Table 12 of the EMP.

Time-concentration plots are provided in Appendix C. Over the past six years (from the spring of 2012 to the fall of 2018), the vast majority of the analytical results show stabilized and/or variable/oscillating concentrations for almost all parameters. Exceptions to this generalization include:

- For the shallow groundwater monitors:
  - M54-4 for alkalinity, DOC, manganese and sodium (increasing trend);
  - M66-2 for chloride, sodium and TDS (downward trend);
  - M67-2 for sodium and TDS (decreasing);
  - M80-2 for alkalinity, and TDS (increasing trend) and chloride (increased to peak of concentration of 85 mg/L in fall 2015 then decreasing trend since that time);
  - M86 for alkalinity (increasing trend) and chloride, DOC, iron, manganese, sodium and TDS (decreasing trend); and,
  - OW37-s for alkalinity (increasing trend).
- For the intermediate bedrock groundwater monitors:
  - M56-2 for alkalinity (increasing);
  - M82-1 for DOC (decreasing);
  - M106 for alkalinity, chloride, sodium and TDS (increasing trend);





- M177 for DOC (increasing);
- M179 for manganese (decreasing);
- M188-1 for sodium (decreasing);
- M185-1 for alkalinity, manganese and TDS (decreasing) and chloride (increasing); and,
- M186 for alkalinity (increasing) and manganese and TDS (decreasing trend).

The observed trends in groundwater geochemistry outlined here are not necessarily indicative of landfill leachate impacts, and should be interpreted with caution. 1,4-dioxane has recently been added to the environmental monitoring program as a primary leachate indicator parameter. Any changes over time for this and other parameters will be used in future environmental monitoring events in the comparative review of groundwater quality results and the evaluation of temporal trends that may be indicative of potential impacts to groundwater from landfill leachate.

### 3.6 ADDITIONAL INVESTIGATIONS

Work outside of the scope of the EMP program was performed throughout the year at the Richmond Landfill Site. Table 9 describes activities performed in 2018.

The principal non-EMP investigations conducted in 2018 were related to the ongoing hydrogeological studies directed by the ERT Order dated December 24, 2015, and follow-up work under direction and oversight from the MECP. These activities were aimed at confirming the spatial extents of the landfill leachate plume delineation in groundwater downgradient from the landfill. Hydrogeological field investigation results were presented and discussed in the latest Site Conceptual Model Update and Contaminant Attenuation Zone Delineation report issued in October 2018<sup>(6)</sup>.

Recently installed monitoring wells M199, M200, M201, M202, M203, M204, M205, M206, M207 were sampled in December 2018 as part of additional sampling events required by the EMP, as per amended ECA Condition No. 8.5(c)iv included in the ERT Order dated July 15, 2015. This condition requires that newly installed wells be tested a minimum of four times on a quarterly basis during the first year after being established. The first two rounds of sampling were reported in the latest update to the SCM<sup>(6)</sup>. The results from the remaining two rounds of sampling at these monitoring locations will be reported in 2019.

Data loggers recording groundwater levels, temperature and electrical conductivity were installed in intermediate bedrock monitoring wells as recommended in the preliminary karst assessment report<sup>(5)</sup>. Monitoring started in March 2017 (May 2017 at the newest wells) and will continue for two years; results will be provided and discussed once monitoring is complete.



A purge well system may be required in the southeast portion of the WM Richmond Landfill property. Four boreholes were drilled and tested in 2018 to conduct a preliminary purge well system evaluation. The results of the preliminary evaluation were presented in a technical memo in October 2018<sup>(8)</sup>.

As requested by MECP, sampling was conducted in December 2018 for analysis of polyfluorinated compounds (PFCs) in leachate, intermediate bedrock groundwater monitoring wells located within the contaminated plume, as well as at three surface water sampling locations.

Other activities conducted in 2018 were related to requirements from a separate ECA associated with the monitoring of on-site Ponds and Leachate, as well as from the Town of Napanee Waste Water Treatment Plant where landfill leachate is hauled and treated.

#### 4. SUMMARY, CONCLUSIONS AND RECOMMENDATIONS

The summer and fall 2018 monitoring programs included the collection of groundwater and surface water samples, as well as landfill gas monitoring, in accordance with the site monitoring requirements outlined in the revised interim EMP (Revision No. 05) dated April 15, 2016, as specified in the Environmental Compliance Approval (ECA) number A371203, issued by MOE January 9, 2012 and amended by Notice No. 1 dated May 3, 2013 and Environmental Review Tribunal (ERT) Order dated December 24, 2015. It is recommended that the EMP be reviewed and amended as appropriate based on the results from, and at the conclusion of investigations conducted as required by the ERT Order and subsequent MECP review and discussion.

The following were completed as part of the summer and fall 2018 EMP monitoring events, between August 9 and September 13, 2018 and October 12 and 18, 2018, respectively:

- Water levels were recorded from groundwater monitoring wells installed in the Shallow groundwater and Intermediate Bedrock Flow Zones, as well as leachate monitoring wells;
- Groundwater monitors completed in the Shallow and Intermediate Bedrock Flow Zones were sampled for analytical testing;
- Surface water locations were sampled for analytical testing;
- Landfill gas monitoring wells were monitored for methane concentrations; and,

---

<sup>8</sup> *Preliminary Purge Well System Evaluation, WM Richmond Landfill, Town of Greater Napanee*, Memorandum dated October 15, 2018



- Quality Assurance/Quality Control (QA/QC) samples were collected, including field duplicate samples, trip blanks and a field blank.

#### 4.1 GROUNDWATER

- Groundwater flow directions interpreted from water elevations measured in monitors were consistent with historical flownets:
  - Shallow groundwater flow on site is influenced by local topographic highs in the southwestern (Empey Hill Drumlin) and eastern (groundwater monitor M96 area) portions of the site, and is characterized by a flow divide with shallow groundwater being directed both to the north (toward Marysville Creek) and the south (toward Beechwood Ditch). South of Beechwood Road shallow groundwater flow converges from local topographic highs to the north and south, and discharges to a local surface water course within a topographically low area running east-west in the central portion of the proposed CAZ;
  - Groundwater in the intermediate bedrock flow zone generally flows to the north, west, and south-southeast relative to the landfill;
- Groundwater quality data from fall 2018 are generally consistent with historical results;
- Slightly elevated groundwater concentrations of a number of water quality parameters are seen in the Shallow Flow Zone within the property in the immediate vicinity of the landfill footprint to the south, north and northwest of the landfill footprint;
- The groundwater geochemical results for the Intermediate Bedrock Flow Zone indicate higher concentrations of water quality parameters associated with landfill leachate impacts to the south-southeast and immediately north of the landfill relative to concentrations west and east of the landfill;
- Recent investigations of the groundwater conditions south of the landfill within the proposed CAZ were completed to delineate the groundwater impacts from the landfill and to define the extent of a contaminant attenuation zone. Results from these investigations were submitted to MECP in October 2018;
- Continued groundwater monitoring within the Shallow and Intermediate Bedrock groundwater flow zones between the landfill footprint and the low-head areas is warranted in order to further examine groundwater quality and any trends over time; and,
- Shallow groundwater monitoring wells M19, M58-4 and M68-4 are damaged and are considered unnecessary for the EMP monitoring program. Upon approval from MECP, these wells will be decommissioned.



## 4.2 SURFACE WATER

- The concentrations observed during summer and fall 2018 monitoring events are within the range of historical monitoring results and indicate that the landfill is not causing adverse impacts to surface water quality;
- The concentrations of total phosphorous and iron exceeded PWQO at numerous locations; copper and cobalt exceeded PWQO at one location; and,
- All other measured parameters were consistent with natural surface water quality and below PWQO.

## 4.3 SUBSURFACE GAS

Measurements for methane gas were between 0 and 20 ppm for the six monitoring locations, well below the LEL for methane of 5% by volume in air (or 50,000 ppm).

## 4.4 LEACHATE GENERATION

An estimate of the amount of leachate generated at the site is provided by the site records of the volume of leachate hauled off-site for treatment at the Town of Greater Napanee Waste Water Treatment Plant. For the 2018 calendar year, the site records show that 16,360.72 m<sup>3</sup> of leachate were generated and hauled for off-site treatment.

## 5. LIMITING CONDITIONS

The summer and fall 2018 monitoring program involved the collection of groundwater (from on-site and off-site monitoring wells), surface water and off site domestic supply wells for analyses. The data collected during this investigation represent the conditions at the sampled locations only.


The conclusions presented in this report represent our professional opinion and are based on the conditions observed on the dates set out in the report, the information available at the time this report was prepared, the scope of work, and any limiting conditions noted herein.

BluMetric Environmental Inc. provides no assurances regarding changes to conditions subsequent to the time of the assessment. BluMetric Environmental Inc. makes no warranty as to the accuracy or completeness of the information provided by others or of the conclusions and recommendations predicated on the accuracy of that information.



This report has been prepared for Waste Management of Canada. Any use a third party makes of this report, any reliance on the report, or decisions based upon the report, are the responsibility of those third parties unless authorization is received from BluMetric Environmental Inc. in writing. BluMetric Environmental Inc. accepts no responsibility for any loss or damages suffered by any unauthorized third party as a result of decisions made or actions taken based on this report.


Respectfully submitted,  
**BluMetric Environmental Inc.**



Madeleine Corriveau, M.Sc., P.Geo.  
Senior Environmental Geochemist



François A. Richard, Ph.D., P.Eng.  
Senior Hydrogeologist



## TABLES



**Table 1: Summary of Environmental Monitoring Program**

Monitoring Locations		Parameter Suite	Monitoring Frequency
<b>Shallow Groundwater Flow Zone Monitors</b>			
M58-4, M68-4, M70-3, M96, M99-2		Groundwater Inorganic & General VOCs	Once each year, in spring
M53-4, M54-4, M66-2, M67-2, M80-2, M81, M85, M86, M87-2, M101, M103, M104, M114-2, OW37-s		Groundwater Inorganic & General VOCs	Twice each year, in spring and fall
<b>Intermediate Bedrock Groundwater Flow Zone Monitors</b>			
M56-2, M58-3, M59-2, M59-4, M91-1, M95-1		Groundwater Inorganic & General VOCs	Once each year, in spring
M5-3, M6-3, M9-2, M9-3, M52-2, M64-2, M70-2, M72, M74, M75, M80-1, M82-1, M82-2, M106, M108, M109-1, M110-1, M114-1, M121, M123, M167, M168, M170, M172, M177, M178R-2, M178R-3, M178R-4, M179, M185-1, M185-2, M186, M187, M188-1, M190, M192, OW1, OW4		Groundwater Inorganic & General VOCs	Twice each year, in spring and fall
<b>Surface Water Sampling Locations</b>			
Beechwood Ditch	S4R, S5 and S8R	Surface Water Inorganic and General	Three times each year, in spring, summer <sup>1</sup> and fall.
Marysville Creek	S2, S3, S6 and S7		
Unnamed water course in central portion of proposed CAZ	S18, S19 and S20		
<b>Leachate Monitoring Locations</b>			
North Chamber, South Chamber, LW-P1 and LW-P2		Leachate Inorganic & General VOCs	Once each year, in spring
<b>Landfill Gas Monitoring Wells</b>			
GM1, GM3, GM4-1, GM4-2, GM5, GM6		% methane by volume	Twice each year, in spring and fall
<b>Off-site Domestic Water Supply Wells</b>			
1441 County Road 1 West 1483 County Road 1 West 1494 County Road 1 West (UNKN) <sup>2</sup> 1499 County Road 1 West 1556 County Road 1 West (UNKN) <sup>2</sup> 1561 County Road 1 West (UNKN) <sup>2,3</sup> 1614 County Road 1 West 1654 County Road 1 West 1680 County Road 1 West 1695 County Road 1 West 1866 County Road 1 West 614 Belleville Road 696 Belleville Road		1,4 dioxane	Once every two years, starting in 2015

<sup>1</sup> The summer monitoring event shall be scheduled after a rainfall of more than 25 mm

<sup>2</sup> The final list of domestic well locations will depend on confirmation of which addresses have drilled wells (locations where well construction is unknown are denoted UNKN). A residential survey will be completed in order to determine which of these locations are to be sampled. Only those residences with drilled bedrock wells that supply water for domestic use will be sampled; residences that use shallow dug wells or cisterns for water supplies are not included in the program.

<sup>3</sup> The well at 1561 Country Road 1 West was confirmed to be a dug well and should not be sampled

**Table 2: Analytical Parameters for Water and Leachate Samples**

<b>Groundwater Inorganic and General Parameters</b>		
Total dissolved solids	Magnesium	Manganese
Alkalinity	Sodium	Ammonia (total)
Conductivity	Potassium	Nitrate
Dissolved organic carbon	Boron	Nitrite
Calcium	Iron	Chloride
		Sulphate
<b>Volatile Organic Compounds (VOCs)</b>		
1,4 Dioxane	1,2-Dichlorobenzene	1,1,2-Trichloroethane
Benzene	1,3-Dichlorobenzene	1,1-Dichloroethane
Toluene	1,4-Dichlorobenzene	1,2-Dichloroethane
Ethylbenzene	Methylene chloride	1,1-Dichloroethylene
m&p-Xylene	Chloromethane	Cis-1,2-Dichloroethylene
o-Xylene	Chloroethane	Trans-1,2-Dichloroethylene
Styrene	1,1,2,2-Tetrachloroethane	Trichloroethylene
1,3,5-Trimethylbenzene	1,1,1,2-Tetrachloroethane	Tetrachloroethylene
Chlorobenzene	1,1,1-Trichloroethane	Vinyl chloride
<b>Surface Water Inorganic and General Parameters</b>		
1,4 Dioxane	Potassium	Nitrate
Total suspended solids	Boron	Nitrite
Total dissolved solids	Cadmium	Chloride
Biological oxygen demand	Chromium (Total, Cr6+, Cr3+)	Sulphate
Chemical oxygen demand	Cobalt	Phenols
Alkalinity	Copper	Total phosphorous
Conductivity	Iron	Naphthalene
Hardness	Lead	
Calcium	Nickel	<i>Field measurements:</i>
Magnesium	Zinc	<i>pH, temperature, conductivity, dissolved</i>
Sodium	Ammonia (total & un-ionized)	<i>oxygen, estimated flow rate</i>
<b>Leachate Inorganic and General Parameters</b>		
Total dissolved solids	Dissolved organic carbon	Ammonia (total)
Conductivity	Boron	Total Kjeldahl nitrogen
Alkalinity	Cadmium	Nitrate
pH	Chromium (total)	Nitrite
Hardness	Cobalt	Chloride
Calcium	Copper	Sulphate
Magnesium	Iron	Total phosphorous
Sodium	Lead	Phenols
Potassium	Manganese	Naphthalene
Biological oxygen demand	Nickel	N-nitrosodimethylamine (NDMA)
Chemical oxygen demand	Zinc	



**Table 3: Groundwater Elevation Monitoring Locations**

Location	Shallow Groundwater Flow Zone	Intermediate Groundwater Flow Zone
West of landfill footprint	M27, M58-4, M67-2, M84, M87-2, M88-2, M89-2, M97, M98, M99-2, M100, M101, M102, OW37-s	M3A-3, M56-2, M58-3, M59-2, M59-3, M59-4, M72, M73, M74, M82-1, M82-2, M91-1, M95-1
East of landfill footprint	M19, M23, M47-3, M68-4, M70-3, M77, M94-2, M96	M50-3, M52-2, M70-2, M108, M170
North of landfill footprint	M35, M60-4, M65-2, M66-2, M83, M85, M86, M103, M104	M46-2, M60-1, OW1
South of landfill footprint; north of Beechwood Road	M12, M14, M15, M18, M41, M53-4, M54-4, M80-2, M81	M9-2, M9-3, M10-1, M49-1, M53-2, M71, M80-1, M105, M106, M107, M109-1, M109-2, M110-1, M111-1, M112-1, M113-1, M192, M193
South of landfill footprint; south of Beechwood Road	M114-2, M115-2	M63-2, M64-2, M114-1, M116, M121, M122, M123, M125, M166, M167, M168, M173, M174, M176, M177, M178R-1, M178R-2, M178R-3, M178R-4, M179, M180, M181-1, M181-2, M182, M185-1, M185-2, M186, M187, M188, M189, M190, M191

Table 4a: Groundwater Elevations - September 13, 2018

Monitoring Well	Water Level (masl)	Monitoring Well	Water Level (masl)	Monitoring Well	Water Level (masl)	Monitoring Well	Water Level (masl)
<b>Shallow Groundwater Flow Zone</b>							
M12	124.51	M54-4	123.85	M83	123.52	M98	128.91
M14	125.14	M58-4	dry	M84	121.93	M99-2	129.05
M15	dry	M60-4	123.67	M85	121.68	M100	123.95
M18	dry	M65-2	122.57	M86	122.80	M101	122.83
M19	damaged	M66-2	122.11	M87-2	122.85	M102	123.07
M23	dry	M67-2	122.11	M88-2	126.40	M103	122.55
M27	125.18	M68-4	dry	M89-2	128.08	M104	122.61
M35	123.52	M70-3	dry	M94-2	124.10	M114-2	122.84
M41	124.78	M77	123.83	M96	126.81	M115-2	123.90
M47-3	123.56	M80-2	123.21	M97	123.60	OW37-s	121.76
M53-4	dry	M81	124.17				
<b>Intermediate Bedrock Groundwater Flow Zone</b>							
M3A-3	124.31	M71	123.52	M113-1	122.48	M178R-4	116.15
M9-2	121.86	M72	122.32	M114-1	118.77	M179	108.84
M9-3	119.27	M73	122.36	M116	118.78	M180	111.19
M10-1	118.81	M74	123.20	M121	118.69	M181-1	95.89
M46-2	123.24	M80-1	122.59	M122	118.70	M181-2	104.94
M49-1	118.50	M82-1	122.46	M123	118.56	M182	89.27
M50-3	124.16	M82-2	122.12	M125	118.80	M185-1	110.53
M52-2	120.01	M91-1	122.50	M166	118.57	M185-2	114.89
M53-2	118.56	M95-1	122.41	M167	118.58	M186	114.27
M56-2	122.52	M105	118.88	M168	118.58	M187	89.83
M58-3	122.54	M106	122.45	M170	118.84	M188-1	95.29
M59-2	122.57	M107	118.87	M173	99.52	M189	104.79
M59-3	122.54	M108	118.59	M174	nm <sup>1</sup>	M190	114.37
M59-4	122.54	M109-1	118.86	M176	108.87	M191	107.72
M60-1	122.42	M109-2	118.88	M177	115.01	M192	118.57
M63-2	120.78	M110-1	118.87	M178R-1	115.41	M193	120.72
M64-2	118.67	M111-1	122.47	M178R-2	116.80 <sup>2</sup>	OW1	122.63
M70-2	119.40	M112-1	122.47	M178R-3	116.71 <sup>2</sup>		

<sup>1</sup> nm = not measured; water level was >30 metres, beyond the length of the water level tape

<sup>2</sup> flowing artesian but pressure gauge did not register; 1 psi assumed (= -0.703 m H<sub>2</sub>O)

Table 4b: Groundwater Elevations - October 12, 2018

Monitoring Well	Water Level (masl)	Monitoring Well	Water Level (masl)	Monitoring Well	Water Level (masl)	Monitoring Well	Water Level (masl)
<b>Shallow Groundwater Flow Zone</b>							
M12	125.10	M54-4	124.06	M83	123.56	M98	129.93
M14	125.72	M58-4	122.99	M84	121.86	M99-2	129.89
M15	125.39	M60-4	123.98	M85	121.78	M100	124.72
M18	dry	M65-2	122.33	M86	123.10	M101	123.41
M19	damaged	M66-2	122.09	M87-2	122.91	M102	124.10
M23	dry	M67-2	122.12	M88-2	126.39	M103	123.06
M27	126.31	M68-4	124.10	M89-2	128.88	M104	123.23
M35	124.07	M70-3	127.03	M94-2	124.07	M114-2	123.52
M41	125.04	M77	123.95	M96	127.04	M115-2	124.67
M47-3	123.98	M80-2	123.40	M97	123.55	OW37-s	121.89
M53-4	124.74	M81	124.35				
<b>Intermediate Bedrock Groundwater Flow Zone</b>							
M3A-3	124.64	M71	123.87	M113-1	122.75	M178R-4	116.51
M9-2	120.42	M72	122.58	M114-1	120.14	M179	109.96
M9-3	120.99	M73	122.64	M116	120.18	M180	111.87
M10-1	120.22	M74	123.51	M121	120.11	M181-1	95.87
M46-2	124.13	M80-1	122.87	M122	120.00	M181-2	105.04
M49-1	120.22	M82-1	122.28	M123	119.77	M182	96.80
M50-3	124.36	M82-2	122.82	M125	120.20	M185-1	112.22
M52-2	119.64	M91-1	122.81	M166	119.78	M185-2	115.93
M53-2	119.97	M95-1	122.68	M167	119.77	M186	114.56
M56-2	122.79	M105	120.41	M168	119.78	M187	94.69
M58-3	122.79	M106	122.73	M170	120.34	M188-1	115.45
M59-2	122.85	M107	120.39	M173	100.38	M189	104.79
M59-3	122.83	M108	119.80	M174	94.70	M190	115.67
M59-4	122.83	M109-1	120.39	M176	109.51	M191	108.39
M60-1	122.28	M109-2	120.42	M177	115.31	M192*	119.38
M63-2	120.94	M110-1	120.39	M178R-1	115.89	M193*	120.84
M64-2	118.78	M111-1	122.73	M178R-2	120.04	OW1	122.76
M70-2	119.84	M112-1	122.78	M178R-3	120.16		

\*Water level measured October 17, 2018





Table 5b: Groundwater Quality Results and Reasonable Use Limits - October 15-18, 2018

		1,4-dioxane	Alkalinity	Chloride	Dissolved Organic Carbon	Iron	Manganese	Sodium	Total Dissolved Solids	1,1-dichloroethylene	Benzene	Ethylbenzene	Xylenes (Total)	Toluene
Name	Date	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
<b>Shallow Groundwater Flow Zone</b>														
<i>RUL</i>		<i>0.001*</i>	<i>390</i>	<i>130</i>	<i>3.6</i>	<i>0.18</i>	<i>0.034</i>	<i>109</i>	<i>452</i>	<i>0.0035</i>	<i>0.0014</i>	<i>0.0013</i>	<i>0.15</i>	<i>0.0121</i>
M54-4	2018-10-16	< 0.001	470	47	3.4	< 0.1	0.023	60	670	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M66-2	2018-10-18		390	110	2.8	0.17	0.019	170	730	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M67-2	2018-10-17	< 0.001	350	5.2	2.5	0.39	0.021	49	315	< 0.0001	< 0.0001	< 0.0001	< 0.0001	0.00027
<i>75% RUL †</i>		<i>n/a</i>	<i>293</i>	<i>98</i>	<i>2.7</i>	<i>0.14</i>	<i>0.026</i>	<i>82</i>	<i>339</i>	<i>0.0026</i>	<i>0.0011</i>	<i>0.00098</i>	<i>0.11</i>	<i>0.0091</i>
M80-2	2018-10-15	< 0.001	370	54	2.4	< 0.1	0.01	22	510	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M87-2	2018-10-15	< 0.001	230	27	1.6	< 0.1	0.008	14	320	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
OW37-s	2018-10-17	< 0.001	160	38	3.1	0.68	0.26	27	165	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.0005
<b>Intermediate Bedrock Groundwater Flow Zone</b>														
<i>RUL</i>		<i>0.001</i>	<i>400</i>	<i>132</i>	<i>3.5</i>	<i>0.18</i>	<i>0.032</i>	<i>106</i>	<i>465</i>	<i>0.0035</i>	<i>0.0014</i>	<i>0.0013</i>	<i>0.15</i>	<i>0.0121</i>
M177	2018-10-16	< 0.001	250	11	2.1	< 0.1	0.007	8.8	305	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M178R-2	2018-10-17	0.0037	370	43	3.9	1	0.062	40	415	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M178R-3	2018-10-17	0.005	390	43	3.8	1.3	0.061	46	410	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M178R-4	2018-10-17	0.0051	400	43	4	< 0.1	0.019	46	455	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M179	2018-10-15	< 0.001	330	63	3.1	0.79	0.043	53	450	< 0.0001	< 0.0001	< 0.0001	< 0.0001	0.00027
M185-1	2018-10-16	< 0.001	300	400	1.9	< 0.1	0.026	350	1070	< 0.0001	0.0001	< 0.0001	< 0.0001	0.00055
M185-2	2018-10-16	< 0.001	290	3.4	2.3	0.12	0.02	3.3	315	< 0.0001	0.00024	< 0.0001	< 0.0001	< 0.0002
M186	2018-10-16	< 0.001	360	1200	1.6	0.43	0.086	700	2260	< 0.0001	0.0002	< 0.0001	0.00021	0.0004
M187	2018-10-18	< 0.001	270	24	2.1	< 0.1	< 0.002	18	290	< 0.0001	< 0.0001	< 0.0001	< 0.0001	0.00024
M188-1	2018-10-16	< 0.001	300	41	1.9	0.11	0.01	61	380	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M190	2018-10-15	< 0.001	290	37	3.6	< 0.1	0.007	23	405	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.0005
<i>75% RUL †</i>		<i>n/a</i>	<i>300</i>	<i>99</i>	<i>2.6</i>	<i>0.14</i>	<i>0.024</i>	<i>80</i>	<i>349</i>	<i>0.0026</i>	<i>0.0011</i>	<i>0.00098</i>	<i>0.11</i>	<i>0.0091</i>
M80-1	2018-10-15	< 0.001	170	25	1.3	< 0.1	0.005	36	175	< 0.0025	< 0.0025	< 0.0025	< 0.0025	< 0.005
M82-1	2018-10-17	< 0.001	340	42	2.6	< 0.1	0.012	92	485	< 0.0001	< 0.0001	< 0.0001	< 0.0001	< 0.0002
M82-2	2018-10-17	< 0.001	330	20	3.3	< 0.1	0.021	16	385	< 0.00025	< 0.00025	< 0.00025	< 0.00025	< 0.0005
M106	2018-10-16	< 0.001	380	1600	1.5	< 0.1	< 0.002	800	2800	0.00068	0.00051	< 0.0001	< 0.0001	0.0015

\* Site-specific RUL for 1,4 dioxane set by ERT Order dated December 24, 2015

† Wells located on the boundary of WM property, including the CAZ boundary, are compared to 75% of RUL concentrations

0.05 Groundwater results exceed Reasonable Use Limits (RUL)

Table 6a: Surface Water Characteristics - August 9, 2018

Date	Parameter		Surface Water Station										
			S2	S3	S4R	S5	S6	S7	S8R	S18	S19	S20	
2018-08-09	Velocity:	m/s	NM	NM	DRY	DRY	DRY	DRY	DRY	DRY	NM	NM	NM
	Depth:	m	0.20	0.14							NM	NM	NM
	Width:	m	0.45	0.25							NM	NM	NM
	Estimated Flow Rate:	m <sup>3</sup> /s	NM	NM							NM	NM	NM

NM: Not Measured (Flow was insufficient, water was ponded, or unable to measure due to vegetation)

Table 6b: Surface Water Characteristics - October 16, 2018

Date	Parameter		Surface Water Station										
			S2	S3	S4R	S5	S6	S7	S8R	S18	S19	S20	
2018-10-16	Velocity:	m/s	NM	NM	DRY	DRY	DRY	DRY	DRY	DRY	NM	NM	NM
	Depth:	m	0.20	NM							NM	0.15	NM
	Width:	m	NM	NM							NM	NM	NM
	Estimated Flow Rate:	m <sup>3</sup> /s	NM	NM							NM	NM	NM

NM: Not Measured (Flow was insufficient, water was ponded, or unable to measure due to vegetation)



Table 7a: Surface Water Quality Results - August 9, 2018

			Marysville Creek				Beechwood Ditch			South of Beechwood Road		
			S2	S3	S6	S7	S5	S4R	S8R	S18	S19	S20
			(upstream)	(downstream)	(downstream)	(downstream)	(upstream)	(downstream)	(downstream)	(upstream)	(downstream)	(downstream)
			2018-09-09	2018-09-09	2018-09-09	2018-09-09	2018-09-09	2018-09-09	2018-09-09	2018-09-09	2018-09-09	2018-09-09
Reading Name	Units	Date	PWQO									
<b>Inorganic and General Parameters</b>												
Alkalinity	mg/L		98	320						130	140	150
Ammonia	mg/L		< 0.15	< 0.15						< 0.15	< 0.15	< 0.15
Ammonia (unionized)	mg/L	0.02	< 0.0005	< 0.0005						< 0.0005	< 0.0005	< 0.0005
Biochemical Oxygen Demand	mg/L		2	< 2						3	< 2	4
Chemical Oxygen Demand	mg/L		62	18						35	42	45
Chloride	mg/L		9	91						13	27	18
Conductivity	µS/cm		550	960						340	590	380
Hardness	mg/L		250	340						140	250	150
Nitrate	mg/L		17.3	< 0.1						< 0.1	< 0.1	< 0.1
Nitrite	mg/L		0.309	< 0.01						< 0.01	< 0.01	< 0.01
Phenols	mg/L	0.001	< 0.001	< 0.001						< 0.001	< 0.001	< 0.001
Phosphorus (total)	mg/L	0.03	0.17	0.13						0.1	0.051	0.19
Sulphate	mg/L		77	52						27	120	23
Total Dissolved Solids	mg/L		425	570						240	410	225
Total Suspended Solids	mg/L		< 10	34						27	< 10	27
<b>Metals</b>												
Boron	mg/L	0.2	0.038	0.09						0.024	0.084	0.051
Cadmium	mg/L		0.0002	< 0.0001						< 0.0001	< 0.0001	< 0.0001
Calcium	mg/L		84	130						55	86	51
Chromium (III)	mg/L	0.0089	< 0.005	< 0.005						< 0.005	< 0.005	< 0.005
Chromium (VI)	mg/L	0.001	< 0.0005	< 0.0005						< 0.0005	< 0.0005	< 0.0005
Chromium (Total)	mg/L		< 0.005	< 0.005						< 0.005	< 0.005	< 0.005
Cobalt	mg/L	0.0009	0.0005	0.0006						0.0006	< 0.0005	< 0.0005
Copper	mg/L	0.005	0.008	< 0.002						< 0.002	< 0.002	< 0.002
Iron	mg/L	0.3	< 0.1	2.2						1.8	< 0.1	1.2
Lead	mg/L	0.005	< 0.0005	< 0.0005						< 0.0005	< 0.0005	< 0.0005
Magnesium	mg/L		12	19						4.2	8.2	6.9
Nickel	mg/L	0.025	0.003	< 0.001						0.001	0.002	0.001
Potassium	mg/L		2.8	12						8	4.5	7.8
Sodium	mg/L		12	64						5.9	22	15
Zinc	mg/L	0.02	0.015	< 0.01						< 0.01	< 0.01	< 0.01
<b>Volatile Organic Compounds (VOCs)</b>												
1,4-dioxane	mg/L	0.02	< 0.001	< 0.001						< 0.001	< 0.001	< 0.001
Naphthalene	mg/L	0.007	< 0.00005	< 0.00005						< 0.00005	< 0.00005	< 0.00005
<b>Field Measurements</b>												
pH (Field)	unitless	6.5-8.5	6.89	7.2						7.55	7.4	7.44
Conductivity (Field)	µS/cm		543	873						328.5	575	394.5
Dissolved Oxygen (Field)	mg/L		4.3	4.28						4.2	3.73	3.94
Temperature (Field)	°C		21.3	18.3						26.6	20.9	23.5

Exceeds PWQO



Table 7b: Surface Water Quality Results - October 16, 2018

			Marysville Creek				Beechwood Ditch			South of Beechwood Road		
			S2	S3	S6	S7	S5	S4R	S8R	S18	S19	S20
			(upstream)	(downstream)	(downstream)	(downstream)	(upstream)	(downstream)	(downstream)	(upstream)	(downstream)	(downstream)
			2018-10-16	2018-10-16	2018-10-16	2018-10-16	2018-10-16	2018-10-16	2018-10-16	2018-10-16	2018-10-16	2018-10-16
Reading Name	Units	Date	PWQO									
<b>Inorganic and General Parameters</b>												
Alkalinity	mg/L		290	310						180	270	250
Ammonia	mg/L		< 0.15	< 0.15						< 0.15	< 0.15	< 0.15
Ammonia (unionized)	mg/L	0.02	< 0.00061	< 0.00061						< 0.00055	< 0.00061	< 0.00065
Biochemical Oxygen Demand	mg/L		< 2	< 2						13	< 2	< 2
Chemical Oxygen Demand	mg/L		26	9.8						33	17	26
Chloride	mg/L		16	100						6	22	19
Conductivity	µS/cm		660	980						400	620	560
Hardness	mg/L		300	340	Dry	Dry	Dry	Dry	Dry	180	280	250
Nitrate	mg/L		< 0.1	< 0.1						< 0.1	< 0.1	< 0.1
Nitrite	mg/L		< 0.01	< 0.01						< 0.01	< 0.01	< 0.01
Phenols	mg/L	0.001	< 0.001	< 0.001						< 0.001	< 0.001	< 0.001
Phosphorus (total)	mg/L	0.03	0.14	< 0.03						0.069	< 0.03	< 0.03
Sulphate	mg/L		40	51						24	31	26
Total Dissolved Solids	mg/L		305	520						235	290	305
Total Suspended Solids	mg/L		17	60						10	< 10	13
<b>Metals</b>												
Boron	mg/L	0.2	< 0.02	0.05						< 0.02	0.032	0.039
Cadmium	mg/L		< 0.0001	< 0.0001						< 0.0001	< 0.0001	< 0.0001
Calcium	mg/L		100	110						68	100	90
Chromium (III)	mg/L	0.0089	< 0.005	< 0.005						< 0.005	< 0.005	< 0.005
Chromium (VI)	mg/L	0.001	< 0.0005	< 0.0005						< 0.0005	< 0.0005	< 0.0005
Chromium (Total)	mg/L		< 0.005	< 0.005						< 0.005	< 0.005	< 0.005
Cobalt	mg/L	0.0009	0.0024	< 0.0005						< 0.0005	< 0.0005	< 0.0005
Copper	mg/L	0.005	< 0.002	< 0.002	Dry	Dry	Dry	Dry	Dry	< 0.002	< 0.002	< 0.002
Iron	mg/L	0.3	2.2	1.2						0.26	< 0.1	0.26
Lead	mg/L	0.005	< 0.0005	< 0.0005						< 0.0005	< 0.0005	< 0.0005
Magnesium	mg/L		15	19						4.2	8.1	8.7
Nickel	mg/L	0.025	0.002	< 0.001						< 0.001	< 0.001	< 0.001
Potassium	mg/L		2.6	13						5.2	3.7	3.8
Sodium	mg/L		14	59						3.8	14	15
Zinc	mg/L	0.02	< 0.01	< 0.01						< 0.01	< 0.01	< 0.01
<b>Volatile Organic Compounds (VOCs)</b>												
1,4-dioxane	mg/L	0.02	< 0.001	< 0.001	Dry	Dry	Dry	Dry	Dry	< 0.001	< 0.001	< 0.001
Naphthalene	mg/L	0.007	< 0.00005	< 0.00005						< 0.00005	< 0.00005	< 0.00005
<b>Field Measurements</b>												
pH (Field)	unitless	6.5-8.5	7.02	7.22						7.3	7.25	7.37
Conductivity (Field)	µS/cm		605	965	Dry	Dry	Dry	Dry	Dry	368	551	553
Dissolved Oxygen (Field)	mg/L											
Temperature (Field)	°C		7.0	8.1						7.5	6.9	7.5

Exceeds PWQO

**Table 8: Subsurface Gas Monitoring Results - October 17, 2018**



<b>Gas Monitor</b>	<b>Location</b>	<b>Reading (ppm)</b>
GM1	North of garage area, south of waste mound	15
GM3	Northeast corner of waste mound	20
GM4-1	Southeast corner of waste mound	5
GM4-2		10
GM5	Northwest corner of waste mound	0
GM6	North of waste mound	0

**Table 9: Additional Investigations**

Description of Activities in 2018	Reporting Completed in 2018	Anticipated / Planned Work in 2019
<p><b>CAZ Investigation:</b></p> <ul style="list-style-type: none"> <li>· Complementary shallow groundwater investigation within the proposed CAZ (including installation and testing of 13 new shallow monitoring locations)</li> <li>· Complementary intermediate bedrock groundwater investigation within the proposed CAZ (including drilling of three new boreholes, which were subsequently decommissioned)</li> <li>· Ongoing data collection and download of data loggers in 10 monitoring wells within the proposed CAZ as recommended by karst expert in 2016 (installed in 2017)</li> <li>· Drilling and testing of four boreholes for the development of a preliminary purge well system design which may be required in the southeast portion of the WM Richmond Landfill property</li> <li>· Sampling for Per- and Polyfluoroalkyl Substances (PFAS) in leachate and selected downgradient groundwater and surface water monitoring locations</li> </ul>	<ul style="list-style-type: none"> <li>- Site Conceptual Model Update and Contaminant Attenuation Zone Delineation (October 2018)</li> <li>- Preliminary Purge Well System Evaluation, WM Richmond Landfill (October 2018)</li> </ul>	<ul style="list-style-type: none"> <li>- Preparation of application to amend ECA to include proposed CAZ</li> <li>- Preparation of revised EMP to reflect new wells and proposed CAZ</li> <li>- Compilation and interpretation of results from data loggers within CAZ</li> <li>- Reporting of final two rounds of groundwater results from newly installed shallow monitoring wells</li> <li>- Evaluation and reporting of PFC sampling results</li> </ul>
<p><b>Town of Greater Napanee WWTP Requirements:</b></p> <ul style="list-style-type: none"> <li>· Monthly North/South Chambers combined leachate sampling (Jan-Dec)</li> </ul>	<ul style="list-style-type: none"> <li>- Monthly reports prepared for the Town of Greater Napanee</li> </ul>	<ul style="list-style-type: none"> <li>- Monitoring and reporting to continue in 2019</li> </ul>
<p><b>ECA Monitoring Requirements - Storm Water Ponds and Leachate:</b></p> <ul style="list-style-type: none"> <li>· Storm Water Ponds <ul style="list-style-type: none"> <li>· Monthly sampling for inorganic and general chemistry parameter lists (March, April, May, October, November, December)</li> <li>· Quarterly Sampling of the ECA Storm water ponds for Toxicity (March, June, September, December)</li> </ul> </li> <li>· Leachate (North Chamber) <ul style="list-style-type: none"> <li>· Quarterly sampling list (March, August, October, December)</li> <li>· Annual sampling chemistry list (May)</li> </ul> </li> </ul>	<ul style="list-style-type: none"> <li>- Monitoring results from the 2017 calendar year for the stormwater ponds and leachate locations were reported in the 2017 Annual Report, prepared by WSP Canada Inc. and dated March 2018</li> </ul>	<ul style="list-style-type: none"> <li>- Monitoring and reporting to continue in 2019</li> </ul>

## FIGURES





**LEGEND**

	Topographic Contour Lines		Lechate Monitoring Well
	Surface Water		Surface Water Monitoring Location
	Property Boundary		Monitoring Well Used to Measure Water Level (Not Sampled)
	Proposed CAZ Boundary		Monitoring Well Used to Measure Water Level and Sampled for Chemistry
			Monitoring Well Sampled for Chemistry (Not used for Water Levels)
			Gas Monitoring Well
			Leachate Chambers

**REFERENCES**

PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC. DO NOT SCALE DRAWING. THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.


-UNITS: METERS  
 -PROJECTION: UTM NAD83 ZONE 18  
 -DATA SOURCE: WM CANADA, BLUMETRIC, HNRD, NRCAN

0 25 50 100 150 200  
 Metres  
 1:8,000

**BluMetric**  
 Environmental

The Tower - The Woolen Mill,  
 4 Catarqui St.,  
 Kingston, Ontario K7K 1Z7  
 TEL: (613) 531-2725  
 FAX: (613) 531-1852  
 Email: info@blumetric.ca  
 Web: http://www.blumetric.ca

<b>CLIENT</b>			
<b>PROJECT</b>			
<b>WASTE MANAGEMENT RICHMOND LANDFILL FALL 2018 SEMI-ANNUAL REPORT</b>			
<b>TITLE</b>			
<b>SITE PLAN AND MONITORING LOCATIONS</b>			
<b>PROJECT #</b>	<b>DATE</b>		
180149-02	January, 2019		
<b>DRAWN</b>	<b>CHECKED</b>	<b>FIG NO.</b>	<b>REV</b>
YL	FR	01	0



**LEGEND**

- Potentiometric Surface (masl)
- Topographic Contour Lines
- Surface Water
- Property Boundary
- Proposed CAZ Boundary
- M53-4 Shallow Groundwater Zone Elevation Monitor
- M5-3 Monitor Not Used in Contouring
- M35 Staff Gauge Location

REV.	DESCRIPTION	YY/MM/DD	BY	CHK
1				

**REFERENCES**  
 PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DIVULGED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC. DO NOT SCALE DRAWING. THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.


**CLIENT**

**PROJECT**  
**WASTE MANAGEMENT RICHMOND LANDFILL  
 FALL 2018 SEMI-ANNUAL REPORT**

**TITLE**  
**SHALLOW GROUNDWATER  
 FLOW ZONE POTENTIOMETRIC SURFACE  
 - SEPT. 13, 2018**

The Tower - The Woolen Mill,  
 4 Cataraqui St.,  
 Kingston, Ontario K7K 1Z7  
 TEL: (613) 531-2725  
 FAX: (613) 531-1852  
 Email: info@blumetric.ca  
 Web: http://www.blumetric.ca

<b>PROJECT #</b> 180149-02		<b>DATE</b> January, 2019	
<b>DRAWN</b> AL	<b>CHECKED</b> FR	<b>FIG NO.</b> 02a	<b>REV</b> 0



**LEGEND**

- Potentiometric Surface (masl)
- Topographic Contour Lines
- Surface Water
- Property Boundary
- Proposed CAZ Boundary
- M53-4 Shallow Groundwater Zone Elevation Monitor
- M5-3 Monitor Not Used in Contouring
- M35 Staff Gauge Location

1				
REV.	DESCRIPTION	YY/MM/DD	BY	CHK

**REFERENCES**  
 PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DIVULGED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC. DO NOT SCALE DRAWING. THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.

0 40 80 160 240  
Metres

**CLIENT**


**PROJECT**  
**WASTE MANAGEMENT RICHMOND LANDFILL  
 FALL 2018 SEMI-ANNUAL REPORT**

**TITLE**  
**SHALLOW GROUNDWATER  
 FLOW ZONE POTENTIOMETRIC  
 SURFACE - OCT. 12, 2018**

The Tower - The Woolen Mill,  
 4 Cataraqui St.,  
 Kingston, Ontario K7K 1Z7  
 TEL: (613) 531-2725  
 FAX: (613) 531-1852  
 Email: info@blumetric.ca  
 Web: http://www.blumetric.ca

PROJECT # <b>180149-02</b>	DATE <b>January, 2019</b>
DRAWN <b>AL/YL</b>	CHECKED <b>FR</b>
FIG NO. <b>02b</b>	REV <b>0</b>






**LEGEND**

- Potentiometric Surface (masl)
- Topographic Contour Lines
- Surface Water
- Property Boundary
- Proposed CAZ Boundary
- M166 Intermediate Groundwater Zone Elevation Monitor
- M189 Monitor Not Used in Contouring


**REFERENCES**  
 PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC.  
 DO NOT SCALE DRAWING.  
 THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.  
 -UNITS: METERS  
 -PROJECTION: UTM NAD83 ZONE 18  
 -DATA SOURCE: WM CANADA, BLUMETRIC, HNRD, NRCAN



**BluMetric**  
 Environmental

The Tower - The Woolen Mill,  
 4 Catarqui St.,  
 Kingston, Ontario K7K 1Z7  
 TEL: (613) 531-2725  
 FAX: (613) 531-1852  
 Email: info@blumetric.ca  
 Web: http://www.blumetric.ca

<b>CLIENT</b>			
<b>PROJECT</b>			
<b>WASTE MANAGEMENT RICHMOND LANDFILL FALL 2018 SEMI-ANNUAL REPORT</b>			
<b>TITLE</b>			
<b>INTERMEDIATE BEDROCK GROUNDWATER FLOW ZONE POTENTIOMETRIC SURFACE - SEPT. 13, 2018</b>			
<b>PROJECT #</b>		<b>DATE</b>	
180149-02		January, 2019	
<b>DRAWN</b>	<b>CHECKED</b>	<b>FIG NO.</b>	<b>REV</b>
AL	FR	03a	0



- LEGEND**
- Potentiometric Surface (masl)
  - Topographic Contour Lines
  - Surface Water
  - Property Boundary
  - Proposed CAZ Boundary
  - M166 Intermediate Groundwater Zone Elevation Monitor
  - M189 Monitor Not Used in Contouring

**REFERENCES**


PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC. DO NOT SCALE DRAWING. THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.

-UNITS: METERS  
 -PROJECTION: UTM NAD83 ZONE 18  
 -DATA SOURCE: WM CANADA, BLUMETRIC, HMRD, NRCAN

0 50 100 200 300 400  
 Metres  
 1:8,000

<b>CLIENT</b>			
<b>PROJECT</b>			
<b>WASTE MANAGEMENT RICHMOND LANDFILL FALL 2018 SEMI-ANNUAL REPORT</b>			
<b>TITLE</b>			
<b>INTERMEDIATE BEDROCK GROUNDWATER FLOW ZONE POTENTIOMETRIC SURFACE – OCT. 12, 2018</b>			
<b>PROJECT #</b>	<b>DATE</b>		
180149-02	January, 2019		
<b>DRAWN</b>	<b>CHECKED</b>	<b>FIG NO.</b>	<b>REV</b>
AL	FR	03b	0

The Tower - The Woolen Mill,  
4 Catarqui St.,  
Kingston, Ontario K7K 1Z7  
TEL: (613) 531-2725  
FAX: (613) 531-1852  
Email: info@blumetric.ca  
Web: http://www.blumetric.ca



OW37-s		M67-2	
Alkalinity	160	Alkalinity	350
Ammonia	< 0.15	Ammonia	0.75
1,4-dioxane	< 0.001	1,4-dioxane	< 0.001

M101		M103	
Alkalinity	480	Alkalinity	720
Ammonia	< 0.15	Ammonia	< 0.15
1,4-dioxane	0.0073	1,4-dioxane	0.013

M86		M66-2		M104	
Alkalinity	360	Alkalinity	390	Alkalinity	1500
Ammonia	< 0.15	Ammonia	0.29	Ammonia	5.1
1,4-dioxane	< 0.001	1,4-dioxane	< 0.001	1,4-dioxane	0.19

M81	
Alkalinity	330
Ammonia	< 0.15
1,4-dioxane	< 0.001

M53-4	
Alkalinity	370
Ammonia	< 0.15
1,4-dioxane	< 0.001


M87-2		M80-2		M114-2		M54-4	
Alkalinity	230	Alkalinity	370	Alkalinity	320	Alkalinity	470
Ammonia	< 0.15	Ammonia	< 0.15	Ammonia	< 0.15	Ammonia	< 0.15
1,4-dioxane	< 0.001	1,4-dioxane	< 0.001	1,4-dioxane	< 0.001	1,4-dioxane	< 0.001

- LEGEND**
- Topographic Contour Lines
  - Surface Water
  - Property Boundary
  - Proposed CAZ Boundary
  - M99-2 Shallow Monitoring Well Sampled for Chemistry
  - M99-2 Shallow Monitoring Well Not Sampled (see text for detailed)
  - 1,4 Dioxane Impacted Area

**NOTE:**  
M58-4 damaged - no sample collected.  
M85 purged dry - no sample collected.

Parameter	Units
Alkalinity	mg/L CaCO <sub>3</sub>
Ammonia	mg/L
1,4-dioxane	mg/L

**REFERENCES**  
PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC.  
DO NOT SCALE DRAWING.  
THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.  
-UNITS: METERS  
-PROJECTION: UTM NAD83 ZONE 18  
-DATA SOURCE: WM CANADA, BLUMETRIC, HNRD, NRCAN




The Tower - The Woolen Mill,  
4 Catarqui St.,  
Kingston, Ontario K7K 1Z7  
TEL: (613) 531-2725  
FAX: (613) 531-1852  
Email: info@blumetric.ca  
Web: http://www.blumetric.ca

**CLIENT**

**PROJECT**  
**WASTE MANAGEMENT RICHMOND LANDFILL  
FALL 2018 SEMI-ANNUAL REPORT**

**TITLE**  
**SHALLOW FLOW ZONE  
CONCENTRATIONS**

<b>PROJECT #</b> 180149-02	<b>DATE</b> January, 2019
<b>DRAWN</b> YL	<b>CHECKED</b> FR
<b>FIG NO.</b> 04	<b>REV</b> 0



OW1	
Alkalinity	440
Ammonia	3.94
1,4-dioxane	< 0.001

M5-3	
Alkalinity	470
Ammonia	1.5
1,4-dioxane	< 0.001

M75	
Alkalinity	440
Ammonia	1.47
1,4-dioxane	< 0.001

OW4	
Alkalinity	960
Ammonia	1.31
1,4-dioxane	0.081

M6-3	
Alkalinity	2000
Ammonia	6.8
1,4-dioxane	0.37

M82-1	
Alkalinity	340
Ammonia	0.92
1,4-dioxane	< 0.001

M82-2	
Alkalinity	330
Ammonia	0.28
1,4-dioxane	< 0.001

M74	
Alkalinity	320
Ammonia	1.22
1,4-dioxane	< 0.001

M72	
Alkalinity	280
Ammonia	0.62
1,4-dioxane	< 0.001

M109-1	
Alkalinity	650
Ammonia	1.31
1,4-dioxane	0.025

M80-1	
Alkalinity	170
Ammonia	0.5
1,4-dioxane	< 0.001

M106	
Alkalinity	380
Ammonia	2.76
1,4-dioxane	< 0.001

M114-1	
Alkalinity	440
Ammonia	0.56
1,4-dioxane	0.0059

M121	
Alkalinity	590
Ammonia	1.89
1,4-dioxane	0.0064

M64-2	
Alkalinity	310
Ammonia	1.09
1,4-dioxane	0.0031

M187	
Alkalinity	270
Ammonia	< 0.15
1,4-dioxane	< 0.001

M177	
Alkalinity	250
Ammonia	0.59
1,4-dioxane	< 0.001

M178R-2	
Alkalinity	370
Ammonia	0.3
1,4-dioxane	0.0037

M178R-3	
Alkalinity	390
Ammonia	0.35
1,4-dioxane	0.005

M178R-4	
Alkalinity	400
Ammonia	0.32
1,4-dioxane	0.0051

M188-1	
Alkalinity	300
Ammonia	0.62
1,4-dioxane	< 0.001

M185-2	
Alkalinity	290
Ammonia	< 0.15
1,4-dioxane	< 0.001

M186	
Alkalinity	360
Ammonia	2.39
1,4-dioxane	< 0.001

M123	
Alkalinity	390
Ammonia	0.32
1,4-dioxane	0.0048

M179	
Alkalinity	330
Ammonia	0.37
1,4-dioxane	< 0.001

M190	
Alkalinity	290
Ammonia	0.16
1,4-dioxane	< 0.001

M185-1	
Alkalinity	300
Ammonia	1.69
1,4-dioxane	< 0.001

M192	
Alkalinity	500
Ammonia	2.28
1,4-dioxane	0.0036

M168	
Alkalinity	470
Ammonia	1.4
1,4-dioxane	0.0074

M167	
Alkalinity	420
Ammonia	2.02
1,4-dioxane	0.0038

M70-2	
Alkalinity	410
Ammonia	2.04
1,4-dioxane	< 0.001

M108	
Alkalinity	540
Ammonia	0.9
1,4-dioxane	0.011

M172	
Alkalinity	570
Ammonia	0.87
1,4-dioxane	0.01

M170	
Alkalinity	740
Ammonia	1.71
1,4-dioxane	0.012

M52-2	
Alkalinity	320
Ammonia	1.83
1,4-dioxane	< 0.001

M110-1	
Alkalinity	690
Ammonia	0.67
1,4-dioxane	0.033


M9-3	
Alkalinity	330
Ammonia	1.3
1,4-dioxane	0.0027

M9-2	
Alkalinity	550
Ammonia	0.9
1,4-dioxane	0.018

- LEGEND**
- Topographic Contour Lines
  - Surface Water
  - - - Property Boundary
  - - - Proposed CAZ Boundary
  - M9-2 Intermediate Monitoring Well Sampled for Chemistry
  - 1,4 Dioxane Impacted Area

Parameter	Units
Alkalinity	mg/L CaCO <sub>3</sub>
Ammonia	mg/L
1,4-dioxane	mg/L

**REFERENCES**  
 PROPRIETARY INFORMATION MAY NOT BE REPRODUCED OR DISCLOSED WITHOUT PRIOR WRITTEN CONSENT OF BLUMETRIC ENVIRONMENTAL INC.  
 DO NOT SCALE DRAWING  
 THIS DRAWING MAY HAVE BEEN REDUCED. ALL SCALE NOTATIONS INDICATED ARE BASED ON 11"x17" FORMAT DRAWINGS.  
 -UNITS: METERS  
 -PROJECTION: UTM NAD83 ZONE 18  
 -DATA SOURCE: WM CANADA, BLUMETRIC, HNRD, NRCAN



The Tower - The Woolen Mill,  
 4 Catarqui St.,  
 Kingston, Ontario K7K 1Z7  
 TEL: (613) 531-2725  
 FAX: (613) 531-1852  
 Email: info@blumetric.ca  
 Web: http://www.blumetric.ca

<b>CLIENT</b>			
<b>PROJECT</b>			
<b>WASTE MANAGEMENT RICHMOND LANDFILL FALL 2018 SEMI-ANNUAL REPORT</b>			
<b>TITLE</b>			
<b>INTERMEDIATE FLOW ZONE CONCENTRATIONS</b>			
<b>PROJECT #</b>	<b>DATE</b>		
180149-02	January, 2019		
<b>DRAWN</b>	<b>CHECKED</b>	<b>FIG NO.</b>	<b>REV</b>
YL	FR	05	0

## APPENDIX A

### Monitoring Well Inventory



## Appendix A: Monitoring Well Inventory

Monitoring Well	Easting	Northing
2054	335293	4902797
2055	335402	4902782
M3A-1	334990	4902928
M3A-2	334990	4902930
M3A-3	334990	4902930
M4-1	335006	4903036
M4-2	335006	4903038
M4-3	335006	4903038
M5-1	335003	4903162
M5-2	335003	4903163
M5-3	335003	4903163
M6-1	335200	4903172
M6-2	335201	4903174
M6-3	335201	4903174
M9-1	335410	4902787
M9-2	335410	4902789
M9-3	335410	4902789
M9R-1	335400	4902787
M10-1	335494	4902596
M10-2	335494	4902596
M10-3	335494	4902594
M12	335500	4902596
M14	335625	4902637
M15	335528	4902695
M16	335447	4902710
M18	335648	4902866
M19	335632	4902944
M23	335602	4903049
M27	334997	4902908
M28	334897	4902853
M29	334924	4902983
M30	334999	4903033
M31	334857	4902977
M35	335458	4903336
M38	335006	4902978
M39	335299	4903310
M41	335368	4902818
M42-1	335006	4903006
M42-2	335007	4903008
M42-3	335007	4903008
M43-1	335475	4902588
M43-2	335476	4902590
M43-3	335476	4902590
M45-1	334790	4904582
M45-2	334790	4904582
M45-3	334790	4904582
M46-1	335185	4903230
M46-2	335185	4903232
M47-1	335552	4903214
M47-2	335552	4903215
M47-3	335552	4903215
M48-1	334838	4902564
M48-2	334839	4902565
M48-3	334839	4902565

## Appendix A: Monitoring Well Inventory

Monitoring Well	Easting	Northing
M49-1	335454	4902658
M49-2	335455	4902660
M49-3	335455	4902660
M50-1	335660	4903247
M50-2	335660	4903248
M50-3	335660	4903248
M51-1	335714	4903073
M51-2	335714	4903075
M51-3	335714	4903075
M52-1	335748	4902939
M52-2	335748	4902940
M52-3	335748	4902940
M53-1	335501	4902651
M53-2	335499	4902650
M53-3	335498	4902650
M53-4	335496	4902649
M54-1	335346	4902623
M54-2	335347	4902622
M54-3	335347	4902620
M54-4	335348	4902618
M55-1	334961	4903151
M55-2	334962	4903149
M55-3	334962	4903148
M55-4	334963	4903146
M56-1	335066	4902508
M56-2	335065	4902545
M57	335418	4902623
M58-1	334760	4902816
M58-2	334760	4902814
M58-3	334761	4902812
M58-4	334761	4902811
M59-1	334609	4903287
M59-2	334607	4903287
M59-3	334606	4903287
M59-4	334604	4903287
M60-1	335044	4903538
M60-3	335079	4903494
M60-4	335077	4903494
M61-1	334457	4903750
M61-2	334456	4903749
M61-3	334455	4903748
M61-4	334454	4903747
M62-1	335166	4904438
M62-2	335168	4904441
M62-3	335166	4904441
M62-4	335165	4904440
M63-1	335424	4902393
M63-2	335425	4902394
M64-1	335585	4902174
M64-2	335585	4902176
M65-1	335297	4903314
M65-2	335298	4903316

## Appendix A: Monitoring Well Inventory

Monitoring Well	Easting	Northing
M66-1	335154	4903218
M66-2	335155	4903219
M67-1	334799	4903089
M67-2	334799	4903090
M68-1	335670	4903504
M68-2	335671	4903502
M68-3	335671	4903500
M68-4	335672	4903499
M69-1	335062	4904299
M69-2	335063	4904298
M69-3	335063	4904296
M69-4	335064	4904295
M70-1	335890	4902862
M70-2	335891	4902860
M70-3	335891	4902858
M71	335390	4902773
M72	334981	4902831
M73	334931	4902891
M74	334950	4902962
M75	335151	4903215
M76	335675	4903217
M77	335685	4903188
M78	335391	4902776
M79	335673	4903215
M80-1	335207	4902532
M80-2	335206	4902534
M81	335275	4902654
M82-1	334640	4903060
M82-2	334641	4903058
M83	335169	4903156
M84	334702	4903072
M85	334999	4903208
M86	335077	4903195
M87-1	334959	4902493
M87-2	334965	4902495
M88-1	334883	4902497
M88-2	334885	4902499
M89-1	334815	4902673
M89-2	334818	4902674
M90-1	334520	4903845
M90-2	334522	4903843
M91-1	334798	4902729
M91-2	334792	4902734
M93	335006	4903908
M94-1	335497	4903519
M94-2	335486	4903526
M95-1	334743	4902908
M95-2	334740	4902917
M96	335774	4903158
M97	335059	4902551
M98	334976	4902730
M99-1	334869	4902646



## Appendix A: Monitoring Well Inventory

Monitoring Well	Easting	Northing
M99-2	334869	4902646
M100	334994	4902965
M101	334949	4903015
M102	334836	4902919
M103	335021	4903101
M104	335150	4903152
M105	335620	4902778
M106	335331	4902549
M107	335650	4902654
M108	335791	4902733
M109-1	335405	4902844
M109-2	335407	4902840
M110-1	335543	4902883
M110-2	335546	4902884
M111-1	335250	4902774
M111-2	335254	4902774
M112-1	335274	4902692
M112-2	335277	4902693
M113-1	335123	4902751
M113-2	335119	4902750
M114-1	335437	4902530
M114-2	335439	4902528
M115-1	335489	4902561
M115-2	335490	4902558
M116	335480	4902494
M117	335586	4902525
M121	335529	4902337
M122	335742	4902433
M123	335905	4902479
M125	335561	4902368
M166	336069	4902589
M167	336266	4902624
M168	336063	4902714
M170	335889	4902865
M171	335759	4903206
M172	335490	4902593
M173	335661	4901812
M174	335961	4901879
M176	336613	4902308
M177	335784	4902084
M178-1	336032	4902203
M178-2	336032	4902206
M178-3	336035	4902209
M178R-1	336008	4902236
M178R-2	336008	4902233
M178R-3	336005	4902233
M178R-4	336002	4902232
M178R-5	335997	4902232
M179	336338	4902357
M180	336801	4902677
M181-1	335912	4901492
M181-2	335912	4901492

## Appendix A: Monitoring Well Inventory

Monitoring Well	Easting	Northing
M182	336402	4901643
M183	336953	4901770
M184	336176	4901998
M185-1	336170	4902151
M185-2	336170	4902151
M186	336509	4902627
M187	335607	4901972
M188-1	335979	4902069
M188-2	335978	4902068
M189	335479	4902099
M190	336274	4902275
M191	336332	4902802
M192	335976	4902826
M193	336082	4902896
M194-1	335564	4901886
M194-2	335568	4901889
M195	335592	4902084
M199	335717	4902027
M200	335793	4902059
M201	335829	4901991
M202	335932	4902013
M203	335709	4902128
M204	335910	4902186
M205	336077	4902128
M206	335938	4902329
M207	336131	4902261
OW1	334995	4903200
OW4	335108	4903128
OW5	335113	4903134
OW36	334799	4903100
OW37-d	334630	4903063
OW37-s	334634	4903062
OW54-d	335406	4902785
OW54-i	335406	4902785
OW54-s	335406	4902785
OW55-d	335376	4903186
OW55-i	335376	4903186
OW55-s	335376	4903184
OW56-d	335106	4903131
OW56-i	335106	4903131
OW56-s	335106	4903129
OW57	335117	4902762
PW1	335465	4902639
PW2	334988	4903095
PW3	335620	4902778
PW4	335626	4902775
PW5	335066	4902547

## APPENDIX B

Results from Analytical Quality Assurance / Quality Control (QA/QC) Program



Appendix B

Summary of Results with Relative Percent Difference (RPD <sup>1</sup>) greater than 20%

Location	Parameter	Unit	Regular Sample	Field Duplicate	RPD (%)	RDL <sup>2</sup>	Comment
M168	Manganese	mg/L	0.005	0.003	50.00	0.002	within 5x RDL
S3 (summer)	Cobalt	mg/L	0.0006	0.001	50.00	0.0005	within 5x RDL
S3 (summer)	Iron	mg/L	2.2	2.9	27.45	0.1	
S3 (summer)	Phosphorus (total)	mg/L	0.13	0.2	42.42	0.03	
S3 (summer)	Total Suspended Solids	mg/L	34	24	34.48	10	within 5x RDL
S3 (fall)	Total Suspended Solids	mg/L	60	93	43.14	10	

<sup>1</sup> RPD (%) = 100 \* ABS (Regular Sample - Duplicate Sample) / ([Regular Sample + Duplicate Sample] / 2 )

<sup>2</sup> RDL = Reportable Detection Limit

Detailed Results from Field Duplicate vs. Regular Samples

Reading Name	Units	M106 2018-10-16 Regular Sample	M106 2018-10-16 Field Duplicate	RPD (%)
Alkalinity	mg/L	380	370	2.67
Ammonia	mg/L	2.76	2.55	7.91
Boron	mg/L	1.8	1.8	0.00
Calcium	mg/L	100	100	0.00
Chloride	mg/L	1600	1600	0.00
Conductivity	µS/cm	5300	5400	1.87
Dissolved Organic Carbon	mg/L	1.5	1.4	6.90
Iron	mg/L	< 0.1	< 0.1	0.00
Magnesium	mg/L	66	66	0.00
Manganese	mg/L	< 0.002	< 0.002	0.00
Nitrate	mg/L	< 0.1	< 0.1	0.00
Nitrite	mg/L	< 0.01	< 0.01	0.00
Potassium	mg/L	21	21	0.00
Sodium	mg/L	800	780	2.53
Sulphate	mg/L	1.4	1.5	6.90
Total Dissolved Solids	mg/L	2800	2840	1.42
1,1,1,2-Tetrachloroethane	mg/L	< 0.0002	< 0.0002	0.00
1,1,1-Trichloroethane	mg/L	< 0.0001	< 0.0001	0.00
1,1,2,2-Tetrachloroethane	mg/L	< 0.0002	< 0.0002	0.00
1,1,2-Trichloroethane	mg/L	< 0.0002	< 0.0002	0.00
1,1-Dichloroethane	mg/L	0.0024	0.0024	0.00
1,1-Dichloroethylene	mg/L	0.00068	0.00069	1.46
1,2-Dichlorobenzene (o)	mg/L	< 0.0002	< 0.0002	0.00
1,2-Dichloroethane	mg/L	< 0.0002	< 0.0002	0.00
1,3,5-Trimethylbenzene	mg/L	< 0.0002	< 0.0002	0.00
1,3-Dichlorobenzene (m)	mg/L	< 0.0002	< 0.0002	0.00
1,4-Dichlorobenzene (p)	mg/L	< 0.0002	< 0.0002	0.00
1,4-Dioxane	mg/L	< 0.001	< 0.001	0.00
Benzene	mg/L	0.00051	0.00051	0.00
Chlorobenzene	mg/L	< 0.0001	< 0.0001	0.00
Chloroethane	mg/L	< 0.0002	< 0.0002	0.00
Chloromethane	mg/L	< 0.0005	< 0.0005	0.00
Cis-1,2-Dichloroethylene	mg/L	< 0.0001	< 0.0001	0.00
Dichloromethane	mg/L	< 0.0005	< 0.0005	0.00
Ethylbenzene	mg/L	< 0.0001	< 0.0001	0.00
m+p-Xylene	mg/L	< 0.0001	< 0.0001	0.00
o-Xylene	mg/L	< 0.0001	< 0.0001	0.00
Styrene	mg/L	< 0.0002	< 0.0002	0.00
Tetrachloroethylene	mg/L	< 0.0001	< 0.0001	0.00
Toluene	mg/L	0.0015	0.0015	0.00
Total Xylenes	mg/L	< 0.0001	< 0.0001	0.00
Trans-1,2-dichloroethylene	mg/L	< 0.0001	< 0.0001	0.00
Trichloroethylene	mg/L	< 0.0001	< 0.0001	0.00
Vinyl Chloride	mg/L	< 0.0002	< 0.0002	0.00

Detailed Results from Field Duplicate vs. Regular Samples

Reading Name	Units	M168 2018-10-17 Regular Sample	M168 2018-10-17 Field Duplicate	RPD (%)
Alkalinity	mg/L	470	470	0.00
Ammonia	mg/L	1.4	1.42	1.42
Boron	mg/L	0.57	0.58	1.74
Calcium	mg/L	140	140	0.00
Chloride	mg/L	300	290	3.39
Conductivity	$\mu$ S/cm	1800	1800	0.00
Dissolved Organic Carbon	mg/L	4.3	4.1	4.76
Iron	mg/L	< 0.1	< 0.1	0.00
Magnesium	mg/L	49	49	0.00
Manganese	mg/L	0.005	0.003	50.00
Nitrate	mg/L	< 0.1	< 0.1	0.00
Nitrite	mg/L	< 0.01	< 0.01	0.00
Potassium	mg/L	14	14	0.00
Sodium	mg/L	150	150	0.00
Sulphate	mg/L	17	18	5.71
Total Dissolved Solids	mg/L	1040	1020	1.94
1,1,1,2-Tetrachloroethane	mg/L	< 0.0005	< 0.0005	0.00
1,1,1-Trichloroethane	mg/L	< 0.00025	< 0.00025	0.00
1,1,2,2-Tetrachloroethane	mg/L	< 0.0005	< 0.0005	0.00
1,1,2-Trichloroethane	mg/L	< 0.0005	< 0.0005	0.00
1,1-Dichloroethane	mg/L	< 0.00025	< 0.00025	0.00
1,1-Dichloroethylene	mg/L	< 0.00025	< 0.00025	0.00
1,2-Dichlorobenzene (o)	mg/L	< 0.0005	< 0.0005	0.00
1,2-Dichloroethane	mg/L	< 0.0005	< 0.0005	0.00
1,3,5-Trimethylbenzene	mg/L	< 0.0005	< 0.0005	0.00
1,3-Dichlorobenzene (m)	mg/L	< 0.0005	< 0.0005	0.00
1,4-Dichlorobenzene (p)	mg/L	< 0.0005	< 0.0005	0.00
1,4-Dioxane	mg/L	0.0074	0.0077	3.97
Benzene	mg/L	< 0.00025	< 0.00025	0.00
Chlorobenzene	mg/L	< 0.00025	< 0.00025	0.00
Chloroethane	mg/L	< 0.0005	< 0.0005	0.00
Chloromethane	mg/L	< 0.0013	< 0.0013	0.00
Cis-1,2-Dichloroethylene	mg/L	< 0.00025	< 0.00025	0.00
Dichloromethane	mg/L	< 0.0013	< 0.0013	0.00
Ethylbenzene	mg/L	< 0.00025	< 0.00025	0.00
m+p-Xylene	mg/L	< 0.00025	< 0.00025	0.00
o-Xylene	mg/L	< 0.00025	< 0.00025	0.00
Styrene	mg/L	< 0.0005	< 0.0005	0.00
Tetrachloroethylene	mg/L	< 0.00025	< 0.00025	0.00
Toluene	mg/L	< 0.0005	< 0.0005	0.00
Total Xylenes	mg/L	< 0.00025	< 0.00025	0.00
Trans-1,2-dichloroethylene	mg/L	< 0.00025	< 0.00025	0.00
Trichloroethylene	mg/L	< 0.00025	< 0.00025	0.00

Detailed Results from Field Duplicate vs. Regular Samples

Reading Name	Units	S3 2018-08-09 Regular Sample	S3 2018-08-09 Field Duplicate	RPD (%)
1,4-Dioxane	mg/L	< 0.001	< 0.001	0.00
Alkalinity	mg/L	320	330	3.08
Ammonia	mg/L	< 0.15	0.15	0.00
Ammonia (unionized)	mg/L	< 0.0005	0.001	0.00
Biochemical Oxygen Demand	mg/L	< 2	< 2	0.00
Boron	mg/L	0.09	0.086	4.55
Cadmium	mg/L	< 0.0001	< 0.0001	0.00
Calcium	mg/L	130	120	8.00
Chemical Oxygen Demand	mg/L	18	18	0.00
Chloride	mg/L	91	92	1.09
Chromium (III)	mg/L	< 0.005	< 0.005	0.00
Chromium (Total)	mg/L	< 0.005	< 0.005	0.00
Chromium (VI)	mg/L	< 0.0005	< 0.0005	0.00
Cobalt	mg/L	0.0006	0.001	50.00
Conductivity	µS/cm	960	950	1.05
Copper	mg/L	< 0.002	< 0.002	0.00
Hardness	mg/L	340	350	2.90
Iron	mg/L	2.2	2.9	27.45
Lead	mg/L	< 0.0005	0.0007	0.00
Magnesium	mg/L	19	19	0.00
Naphthalene	mg/L	< 0.00005	< 0.00005	0.00
Nickel	mg/L	< 0.001	0.001	0.00
Nitrate	mg/L	< 0.1	< 0.1	0.00
Nitrite	mg/L	< 0.01	< 0.01	0.00
Phenols	mg/L	< 0.001	< 0.001	0.00
Phosphorus (total)	mg/L	0.13	0.2	42.42
Potassium	mg/L	12	12	0.00
Sodium	mg/L	64	61	4.80
Sulphate	mg/L	52	51	1.94
Total Dissolved Solids	mg/L	570	530	7.27
Total Suspended Solids	mg/L	34	24	34.48
Zinc	mg/L	< 0.01	< 0.01	0.00

Detailed Results from Field Duplicate vs. Regular Samples

Reading Name	Units	S3 2018-10-16 Regular Sample	S3 2018-10-16 Field Duplicate	RPD (%)
1,4-Dioxane	mg/L	< 0.001	< 0.001	0.00
Alkalinity	mg/L	310	310	0.00
Ammonia	mg/L	< 0.15	< 0.15	0.00
Ammonia (unionized)	mg/L	< 0.00061	< 0.00061	0.00
Biochemical Oxygen Demand	mg/L	< 2	< 2	0.00
Boron	mg/L	0.05	0.049	2.02
Cadmium	mg/L	< 0.0001	< 0.0001	0.00
Calcium	mg/L	110	110	0.00
Chemical Oxygen Demand	mg/L	9.8	8.4	15.38
Chloride	mg/L	100	97	3.05
Chromium (III)	mg/L	< 0.005	< 0.005	0.00
Chromium (Total)	mg/L	< 0.005	< 0.005	0.00
Chromium (VI)	mg/L	< 0.0005	< 0.0005	0.00
Cobalt	mg/L	< 0.0005	< 0.0005	0.00
Conductivity	µS/cm	980	980	0.00
Copper	mg/L	< 0.002	< 0.002	0.00
Hardness	mg/L	340	340	0.00
Iron	mg/L	1.2	1	18.18
Lead	mg/L	< 0.0005	< 0.0005	0.00
Magnesium	mg/L	19	19	0.00
Naphthalene	mg/L	< 0.00005	< 0.00005	0.00
Nickel	mg/L	< 0.001	0.001	0.00
Nitrate	mg/L	< 0.1	< 0.1	0.00
Nitrite	mg/L	< 0.01	< 0.01	0.00
Phenols	mg/L	< 0.001	< 0.001	0.00
Phosphorus (total)	mg/L	< 0.03	< 0.03	0.00
Potassium	mg/L	13	12	8.00
Sodium	mg/L	59	58	1.71
Sulphate	mg/L	51	52	1.94
Total Dissolved Solids	mg/L	520	500	3.92
Total Suspended Solids	mg/L	60	93	43.14
Zinc	mg/L	< 0.01	< 0.01	0.00

Detailed Results from Blank Samples - Fall 2018

Reading Name	Units	2018-10-15 Field Blank	2018-10-17 Trip Blank	2018-10-17 Trip Blank
<b>General/Inorganic Parameters</b>				
Alkalinity	mg/L	2.3	-	-
Ammonia	mg/L	< 0.15	-	-
Boron	mg/L	< 0.02	-	-
Calcium	mg/L	< 0.2	-	-
Chloride	mg/L	< 1	-	-
Conductivity	µS/cm	1.6	-	-
Dissolved Organic Carbon	mg/L	0.6	-	-
Iron	mg/L	< 0.1	-	-
Magnesium	mg/L	< 0.05	-	-
Manganese	mg/L	< 0.002	-	-
Nitrate	mg/L	< 0.1	-	-
Nitrite	mg/L	< 0.01	-	-
Potassium	mg/L	< 0.2	-	-
Sodium	mg/L	< 0.1	-	-
Sulphate	mg/L	< 1	-	-
Total Dissolved Solids	mg/L	< 10	-	-
<b>Volatile Organic Compounds (VOCs)</b>				
1,1,1,2-Tetrachloroethane	mg/L	< 0.0002	< 0.0002	< 0.0002
1,1,1-Trichloroethane	mg/L	< 0.0001	< 0.0001	< 0.0001
1,1,2,2-Tetrachloroethane	mg/L	< 0.0002	< 0.0002	< 0.0002
1,1,2-Trichloroethane	mg/L	< 0.0002	< 0.0002	< 0.0002
1,1-Dichloroethane	mg/L	< 0.0001	< 0.0001	< 0.0001
1,1-Dichloroethylene	mg/L	< 0.0001	< 0.0001	< 0.0001
1,2-Dichlorobenzene (o)	mg/L	< 0.0002	< 0.0002	< 0.0002
1,2-Dichloroethane	mg/L	< 0.0002	< 0.0002	< 0.0002
1,3,5-Trimethylbenzene	mg/L	< 0.0002	< 0.0002	< 0.0002
1,3-Dichlorobenzene (m)	mg/L	< 0.0002	< 0.0002	< 0.0002
1,4-Dichlorobenzene (p)	mg/L	< 0.0002	< 0.0002	< 0.0002
1,4-Dioxane	mg/L	< 0.001		
Benzene	mg/L	< 0.0001	< 0.0001	< 0.0001
Chlorobenzene	mg/L	< 0.0001	< 0.0001	< 0.0001
Chloroethane	mg/L	< 0.0002	< 0.0002	< 0.0002
Chloromethane	mg/L	< 0.0005	< 0.0005	< 0.0005
Cis-1,2-Dichloroethylene	mg/L	< 0.0001	< 0.0001	< 0.0001
Dichloromethane	mg/L	< 0.0005	< 0.0005	< 0.0005
Ethylbenzene	mg/L	< 0.0001	< 0.0001	< 0.0001
m+p-Xylene	mg/L	< 0.0001	< 0.0001	< 0.0001
o-Xylene	mg/L	< 0.0001	< 0.0001	< 0.0001
Styrene	mg/L	< 0.0002	< 0.0002	< 0.0002
Tetrachloroethylene	mg/L	< 0.0001	< 0.0001	< 0.0001
Toluene	mg/L	< 0.0002	< 0.0002	< 0.0002
Total Xylenes	mg/L	< 0.0001	< 0.0001	< 0.0001
Trans-1,2-dichloroethylene	mg/L	< 0.0001	< 0.0001	< 0.0001
Trichloroethylene	mg/L	< 0.0001	< 0.0001	< 0.0001
Vinyl Chloride	mg/L	< 0.0002	< 0.0002	< 0.0002




## APPENDIX C


### Time-Concentration Plots from Groundwater Trigger Wells




# Shallow Flow Zone




# Shallow Flow Zone




# Shallow Flow Zone




# Shallow Flow Zone




# Shallow Flow Zone



# Shallow Flow Zone




# Shallow Flow Zone








# Intermediate Flow Zone




# Intermediate Flow Zone






# Intermediate Flow Zone



# Intermediate Flow Zone





## BluMetric Environmental Inc.

### BluMetric Offices

---

4-41 de Valcourt Street  
Gatineau, Québec  
Canada J8T 8G9  
Téléphone: 819 243.7555  
Télécopieur: 819 243.0167  
[gatineau@blumetric.ca](mailto:gatineau@blumetric.ca)

3108 Carp Road  
PO Box 430  
Ottawa, Ontario  
Canada K0A 1L0  
Tel: 613.839.3053  
Fax: 613.839.5376  
[ottawa@blumetric.ca](mailto:ottawa@blumetric.ca)

825 Milner Avenue  
Toronto, Ontario  
Canada M1B 3C3  
Tel: 877.487.8436  
[toronto@blumetric.ca](mailto:toronto@blumetric.ca)

276, Saint-Jacques Street  
Suite 818  
Montréal, Québec  
Canada H2Y 1N3  
Téléphone: 514 844.7199  
Télécopieur: 514 841.9111  
[montreal@blumetric.ca](mailto:montreal@blumetric.ca)

4 Cataragui Street  
The Tower, The Woolen Mill  
Kingston, Ontario  
Canada K7K 1Z7  
Tel: 613.531.2725  
Fax: 613.531.1852  
[kingston@blumetric.ca](mailto:kingston@blumetric.ca)

---

4916 – 49<sup>th</sup> Street  
Yellowknife, NT  
Canada X1A 1P3  
Tel: 867.873.3500  
Fax: 867.873.3499  
[yellowknife@blumetric.ca](mailto:yellowknife@blumetric.ca)

171 Victoria Street North  
Kitchener, Ontario  
Canada N2H 5C5  
Tel: 519.742.6685  
Fax: 519.742.9810  
[kitchener@blumetric.ca](mailto:kitchener@blumetric.ca)

102-957 Cambrian Heights Drive  
Sudbury, Ontario  
Canada P3C 5S5  
Tel: 705.525.6075  
Fax: 705.525.6077  
[sudbury@blumetric.ca](mailto:sudbury@blumetric.ca)

PO Box 36  
Shebandowan, Ontario  
Canada P0T 2T0  
Tel: 807.707.1687  
[thunderbay@blumetric.ca](mailto:thunderbay@blumetric.ca)

[www.blumetric.ca](http://www.blumetric.ca)